


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. Twp. Rge. (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
Lease Owner Crown Oil Company, Inc.
Lease Name Soeken Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4-8-51 19____
Plugging completed 4-13-51 19____
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"	3815'	2949'
				8-5/8"	304'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rocked hole to 3770' and ran 5 sacks cement. Mudded hole to 250', set rock bridge from 304' to 2908' and ran 15 sacks cement. Mudded hole to 30' and ran 10 sacks cement on top. Well completed.

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1951 4-21-51
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Crown Oil Company, Inc.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Ralph E. Mullin, President (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CROWN OIL COMPANY, INC.
(Signature) Ralph E. Mullin President

P.O. Box 164, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of April, 1951
Henry Seacock Notary Public.

My commission expires June 13, 1951
23-5091-s 8-50-10M

PLUGGING
FILE SEC-10 P. 22 D. 13W
BOOK PAGE 74 LOSS

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas


Company - CROWN OIL CO.
Farm - Sockon No. 1

SEC. 10 T. 22 R. 13W
NW 1/4 SE

Total Depth. 3815
Comm. 4-22-50 Comp. 5-8-50
Shot or Treated. 1200 az.
Contractor. Hilton Drlg. Co.
Issued. 10-21-50

County. Stafford

KANSAS



Elevation. 1890 D.F.

Production. 26 bbls. / 50% wtr.

CASING:

8 5/8" 304' con. w/225 sx.
5 1/2" 3815' con. w/125 sx.

Figures Indicate Bottom of Formations.

collar	4
surface sand &	
shale	170
clay	200
sand	250
red bed	740
anhyd.	765
shale & shells	930
shale, shells &	
salt	1175
shale & shells	1645
limo	1745
limo brkn & shale	1870
limo & sand	1965
limo & shale	2060
limo brkn	2175
limo & shale	2343
limo brkn & shale	2440
limo & shale	2625
shale, limo &	
shells	2710
shale & limo	2965
limo brkn & shale	3050
limo & shale	3175
limo	3662
Congl., limo &	
sand	3685
chert	3736
limo	3815
Total Depth	

Tops:	
Hobnor shale	3244
Brown limo	3371
Lansing	3391
Congl.	3661
Viola chert	3683
Simpson	3730
Arb.	3781

3552-60 op. 45" rec. 10' mud.
18/3778-80 1200 az.

PLUGGING
FILE SEC 10 T 24 R 13W
BOOK PAGE 74 LINE 4

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1951
CONSERVATION DIVISION
Wichita, Kansas