


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 6 Twp. 22 Rge. (E) 13 (W)
Location as "NE/CNW*SW*" or footage from lines NW SE NW
Lease Owner National Cooperative Refinery Association
Lease Name Curtis "A" Well No. 4
Office Address P. O. Box #6, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 9, 1954
Application for plugging filed September 4, 1968
Application for plugging approved September 6, 1968
Plugging commenced September 13, 1968
Plugging completed September 18, 1968
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production August 27, 1968
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren
Producing formation Lansing Depth to top 3498' Bottom 3512' Total Depth of Well 3615 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	RECEIVED STATE CORPORATION COMMISSION SEP 24 1968 CONSERVATION DIVISION Wichita, Kansas			8 5/8"	340'	None
				5 1/2"	3615'	2650'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Pushed plug to 3400'. Sanded hole to 3375', dumped 5 sacks cement. Shot 5 1/2" casing off and pulled 83 joints (2650'). Set plug at 275', rock bridge to 260', dumped 3 sacks cement. Bailed hole down, dumped 3 1/2 yards ready-mix concrete on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc.
Address 320 North Park, Stafford, Kansas 67578


STATE OF Kansas, COUNTY OF Barton, ss.
Joseph Hertel (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, filed and that the same are true and correct. So help me God.

(Signature) Joseph Hertel
P. O. Box #6, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd. day of September, 19 68

My commission expires October 23, 1970

Irene Kelly Marney
Irene Kelly Marney Notary Public.



THE VICKERS PETROLEUM CO., INC.

Curtis "A", Well #4
 Approx. 1585' N L 330' W L
 NW 1/4 Sec. 6-22S-13W
 Stafford County, Kansas

Casing Record:
 8 5/8" @ 340' w/ 275 sx.
 5 1/2" @ 3615' w/ 150 sx.

Commenced: February 16, 1954
 Completed: March 9, 1954

Elevation: 1919 R. B. (4' above G. L.)
 Potential: Pump 71 B.O.P.D. no water.

LOG

			<u>Tops</u>	
			<u>Schlumberger</u>	<u>Sample</u>
Sand	0-200			
Shale & Sand	200-300			
Red Rock & Red Beds	300-340			
Red Beds & Sand	340-797			
Anhydrite	797-820	Heebner	3240	3241
Shale & Shells	820-945	Toronto	3260	3261
Shale & Lime	945-1355	Douglas	3273	3273
Shale & Salt	1355-1580	Brown Lime	3364	3365
Lime & Shale	1580-1850	Lansing	3376	3377
Lime	1850-2008	T. D.	3614	3615
Lime & Shale	2008-2350			
Shale & Lime	2350-2485			
Lime & Shale	2485-2690			
Shale & Lime	2690-2815			
Lime & Shale	2815-2998			
Lime	2998-3241			
Black Shale	3241-3246			
Lime	3246-3249			
Shale	3249-3261			
Lime	3261-3273			
Shale	3273-3365			
Lime	3365-3368			
Shaley Lime	3368-3373			
Shale	3373-3377			
Lime	3377-3599			
Shale	3599-3604			
Lime	3604-3609			
Shale	3609-3615 T.D.			

Cleanout to 3595.
 42 perfs 3498-3512 S. G. & oily mud.
 Bail 5 G.O.P.H. Fill up 78 gal. oil
 15 hrs. Acidize w/ 1000 gal. Swab
 5 B.O.P.H.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 6 1968
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this Log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM COMPANY, INC.

BY *[Signature]*

Sworn & subscribed to before me this 26 day of March, 1954.

My Commission Expires August 13, 1957.

Allen J. Denton
 Notary Public