

API NUMBER 15-185-11204-0000

LEASE NAME George Schmid

WELL NUMBER 4

SPOT LOCATION NW SW SW

SEC. 6 TWP. 22 SRGE. 13 ~~NE~~ or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 1/9/86

Plugging Completed 1/28/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texaco Inc for Texaco Producing Inc.

ADDRESS Box 2420, Tulsa, OK 74102

PHONE # (918) 560-6000 OPERATORS LICENSE NO. 4742

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? J. H. Metz, Inspector

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Arbuckle Depth to top 3704' bottom 3716 T.D. 3716'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	576	none
				5 1/2	3704	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Well plugged as follows: 3714-3514 30 sx cmt; 3514-2500 w/mud; 2500-2350 w/15 sx cmt; 2350-900 w/mud; 900-3' w/115 sx in 5-1/2" csg; 617-3' w/85 sxs between 8-5/8 & 5-1/2"; 3' to surface w/native dirt; welded on plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor D S & W Well Svs License No. 6901

Address Box 231, Claflin, Ks 67525

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

R. W. BLOHM, Ass't District Manager (employee of operator) ~~x~~
~~x~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 2420, Tulsa, Ok 74102

SUBSCRIBED AND SWORN TO before me this 12th day of Feb, 1986

[Signature]
Notary Public
STATE CORPORATION COMMISSION

My Commission expires: 8-3-88

2-14-86

FEB 14 1986

Form CP-4
Revised 01-84