


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Stafford County, Sec. 6 Twp. 22 Rge. 13 (E) (W) X  
Location as "NE/CNW%SW%" or footage from lines NW SW NW  
Lease Owner National Cooperative Refining Assoc.  
Lease Name Curtis "A" Well No. #3  
Office Address Box 6, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19\_\_\_\_  
Application for plugging filed 19\_\_\_\_  
Application for plugging approved 19\_\_\_\_  
Plugging commenced 4-15-68 19\_\_\_\_  
Plugging completed 4-18-68 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3726 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3722'	2928.65'
				8 5/8"	340'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 3700'. Mixed and ran 5 sacks cement thru dump bailer.  
Mudded hole to 330', set 10' rock bridge. Mixed and ran 5 sacks cement thru dump bailer. Bailed hole dry. Filled hole with 4 yards ready-mix from 300' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of April, 19 68

My commission expires 21 October 1968  
Sidney D. Miller  
Notary Public.

## VICKERS PETROLEUM CO., INC.

Curtis "A", Well #3  
NW SW NW 6-22S-13W  
Stafford County, Kansas

Casing Record:  
8 5/8" @ 340' w/ 250 sx.  
5 1/2" @ 3722' w/ 125 sx.

Commenced: November 30, 1953  
Completed: December 19, 1953

Elevation: 1919 R. B.  
Potential Pump 46 B.O.P.D. / 35% water.

LOG

Sand & Red Beds	0-341
Red Beds	341-390
Shale & Shells	390-788
Anhydrite	788-812
Shale & Shells	812-1360
Salt & Shale	1360-1555
Lime & Shale	1555-1730
Lime	1730-1775
Lime & Shale	1775-1954
Lime	1954-2120
Lime & Shale	2120-2400
Shale & Lime	2400-2810
Lime & Shale	2810-3115
Lime w/ shale streaks	3115-3275
Sand & Shale	3275-3365
Lime & Shale Streaks	3365-3632
Conglomerate	3632-3638
Chert	3638-3671
Shale w/ sand streaks	3671-3721
Dolomite	3721-3723 R.T.D.
D.D. w/ Cable Tools	3723-3726 1/2 T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

TOPS:

Heebner	3243
Brown lime	3365
Lansing	3378
Conglomerate	3632
Viola	3638
Simpson	3671
Arbuckle	3721

I hereby certify that this Log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

BY A. C. Fowles

Sworn and subscribed to before me this 18 day of January, 1954.

Allen J. Denton  
Notary Public

My Commission Expires August 13, 1957.