


Give All Information Completely  
Make Required Affidavits  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 6 Twp. 22S Rge. 13 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines C NW/4 NW/4  
Lease Owner National Cooperative Refinery Association  
Lease Name Curtis "B" Well No. 3  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed March 3 19 53  
Application for plugging filed June 7 19 63  
Application for plugging approved June 11 19 63  
Plugging commenced September 26 19 63  
Plugging completed September 30 19 63  
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production May 15 19 63  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3610 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	343'	none
				5 1/2"	3609'	2990

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped 1 sack of cement at 3300'. Shot 5 1/2" casing off at 2965'. Pulled 97 joints, 2990', of 5 1/2" casing. Mudded hole to 300', set 10' rock bridge, dumped 6 sacks of cement. Hole tested dry. Dumped 19 sacks of cement, and mudded hole to 40', set 10' rock bridge plus 10' cement on up to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 10 1963

CONSERVATION DIVISION  
Wichita, Kansas

10-10-63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc.  
Address 411 South Buckeye, Stafford, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
G. R. Sears (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. R. Sears  
305 Rule Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 63

My commission expires April 29, 1965

Norma Richey  
Norma Richey Notary Public.



## THE VICKERS PETROLEUM CO., INC.

Curtis "B" Well #3  
240' WL & 660' NL  
NW NW Sec. 6-22S-13W  
Stafford County, Kansas

Casing Record  
8 5/8" @ 343' with 250 sx  
5 1/2 " @ 3609 with 125 sx

Commenced: February 10, 1953  
Completed: March 3, 1953

Elevation: 1917 R.B.  
Potential: Flow 546 BOPD / 1% wat.

LOG

Sand	0- 300	Perforated 36 shts, 3405-3413
Shale & Sand	300- 315	Acidized with 2000 gal.
Red Beds	315- 343	
Red Beds & Sand	343- 798	
Anhydrite	798- 823	
Red Beds, Shale & Shells	823-1285	
Shale & Shells	1285-1360	
Shale & Salt	1360-1550	
Shale & Lime	1550-1585	
Lime & Shale	1585-1720	
Lime & Sand	1720-1770	
Lime & Shale	1770-1815	
Lime, Shale & Sand	1815-2035	
Lime	2035-2135	
Lime & Shale	2135-2505	
Shale & Lime	2505-2820	
Lime & Shale	2820-3010	
Lime	3010-3050	
Lime & Shale	3050-3155	
Lime	3155-3244	
Black shale	3244-3248	
Lime	3248-3253	
Shale	3253-3260	
Lime	3260-3277	
Shale & Sandy shale	3277-3367	
Lime	3367-3373	
Shale	3373-3379	
Lime & little shale	3379-3610 T.D.	

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 11 1963

CONSERVATION DIVISION  
Wichita, Kansas

## SAMPLE TOPS:

Heebner 3244'  
Toronto 3260'  
Douglas 3277'  
Brown lime 3367'  
Lansing 3379'  
T.D. 3610 in Lansing K.C.

I hereby certify that this Log is true and correct to the best of my knowledge and belief.

VICKERS PETROLEUM CO., INC.

BY James T. Walker

Sworn and subscribed to before me this 11 day of March, 1953.

Allen P. Denton  
Notary Public

My Commission expires August 13, 1953.