

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

A 4x4 grid of squares, intended for drawing a face. The grid is composed of 16 squares arranged in 4 rows and 4 columns.

**Locate well correctly on above
Section Plat**

Stafford	County, Sec. 6	Twp. 22	Rge. (E) 13	(W)
Location as "NE¼NW¼SW¼" or footage from lines C. S. L. S. E. N. W.				
Lease Owner Vickers McMorrow				
Lease Name Curtis				Well No. 2
Office Address 201 W-K-H Bldg., Wichita, Kansas				
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole				
Date well completed March 20				1943
Application for plugging filed March 20				1943
Application for plugging approved March 20				1943
Plugging commenced March 20				1943
Plugging completed March 20				1943
Reason for abandonment of well or producing formation Dry				

If a producing well is abandoned, date of last production.....19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....Yes

Name of Conservation Agent who supervised plugging of this well..... E. I. Alexander

Producing formation..... Viola..... Depth to top..... 3711..... Bottom..... 3720..... Total Depth of Well..... 3720..... Feet

Show depth and thickness of all water, oil and gas formations.



OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Mudded hole from 3720' to 335'. Set bridge and cemented with 15 sacks of cement. Top of cement 305'. Mudded hole to 26'. Set bridge, and cemented 6'. Mudded to surface.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... John M. Little, The Vickers Petroleum Co., Inc.,
Address..... 201 W-K-H Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John M. Little (employee of owner) or ~~(owner or operator)~~ of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

201 W-K-H Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1943

My commission expires October 24, 1944.

Notary Public.

THE VICKERS PETROLEUM CO., INC. & McMORROW

Curtis No. 2
 CSL SE NW
 Stafford County, Kansas

CASING RECORD:

10 3/4" Surface casing cemented @
 334' with 275 sacks.

Commenced: March 9, 1943
 Completed: March 20, 1943

Elevation: _____

LOG

Surface	0 - 336
Shale & Red Bed	336 - 500
Red Bed	500 - 780
Anhydrite	780 - 800
Shale & Red Bed	800 - 1000
Shale, Shells, Red Bed	1000 - 1260
Salt & Shale	1260 - 1550
Shale & Shells	1550 - 1640
Shale	1640 - 1700
Anhydrite & Lime	
Shells	1700 - 1760
Lime Broken	1760 - 1940
Lime & Chert	1940 - 2045
Broken Lime	2045 - 2155
Lime	2155 - 2220
Shale & Lime	2220 - 2330
Shale & Lime Shells	2330 - 2465
Shale & Lime	2465 - 3005
Lime	3005 - 3355
Shale & Lime	3355 - 3411
Lime	3411 - 3700
Conglomerate	3700 - 3711
Lime	3711 - 3720

Tops

Lansing (Brown)	3411
Lansing (White)	3421
Cherty Conglomerate	3700
Viola	3711
Total Depth	3720

No shows.

Dry and Abandoned.

I hereby certify that this log is true and correct to the best of my knowledge and belief.

MAR 24 1943

THE VICKERS PETROLEUM CO., INC.

By

A. S. Bunte

Subscribed and sworn to before
 me this 23rd day of March, 1943.

[Signature]
 Notary Public

My commission expires October 24, 1944.

6 22 134
 68 12