


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-009-15680-8000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 4 Twp. 16s Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner American Petrofina Company of Texas
Lease Name Casey Well No. 1
Office Address Box 209 Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed February 26 19 38
Application for plugging filed December 4 19 59
Application for plugging approved December 7 19 59
Plugging commenced January 8 19 60
Plugging completed January 20 19 60
Reason for abandonment of well or producing formation Insufficient Production

If a producing well is abandoned, date of last production January 30 19 55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Truan
Producing formation Arbuckle Depth to top 3330' Bottom 3333' Total Depth of Well 3333' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	215'	10 3/4"	215	0
		0	3323'	7"	3323'	312'
		0	3313'	5 1/2"	3313'	2781'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Run 5 sacks of cement at 2950'

Mudded to 215'

Set rock bridge to 205'

Run 30 sacks of cement at 205'

Mudded to 40'

Set rock bridge to 35'

Run 15 sacks of cement to cap.

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C. E. Shull Casing Pulling Company
Address Box 558 Great Bend, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
LEVI B. SHERMAN (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Levi B. Sherman
Box 209 Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 19 60

My commission expires 10-2-60

Carol Bennett
Notary Public.



C. E. Shull Casing Pulling Company

C. E. SHULL, Manager

Post Office Box 558

Telephone Gladstone 3-5901

GREAT BEND, KANSAS

Pulling and Plugging Oil and Gas Wells

Invoice No. 474

Customer's
Order No. _____

American Petrofina Co. of Texas

January 23, 1969

Great Bend, Kansas,

(Please Make Remittance to This Office).

19

Russell, Kansas

Net: No Discount.

TERMS:

Pulling 5½" & 7" casing, plugging and abandoning your Casey Well #1, Sec. 4-16S-12E, in Barton County, Kansas as authorized. Operations completed as directed by Mr. Truan of Kansas Conservation Division.

1-10-60	Driving bridge down	8 hrs.	
1-11-60	Driving bridge & cementing	8 hrs.	
1-12-60	Working & ripping 5½" csg.	4 hrs.	
1-15-60	Working & ripping 7" csg.	8 hrs.	
1-16-60	Working & ripping 7" csg.	4 hrs.	
1-20-60	Mudding & cementing	<u>6 hrs.</u>	
	Total day work	38 hrs.	@ \$7.00 per hr. \$266.00
	Pulled 2781.30' of 5½" casing		@ 20¢ per ft. 556.26
	Pulled 342.05' of 7" casing		@ 20¢ per ft. <u>68.41</u>
			\$890.67

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1969

Federal Soc. Sec. No. 48-0532689

CONSERVATION DIVISION
Wichita, Kansas

Brief Plugging Record on
American Petrofina Co. of Texas's
Casey Well #1, in
Barton County, Kansas

Total depth 3333'

5½" casing set at 3313'

7" casing set at 3323'

Squeezed with 150 sacks of cement

10½" casing set at 215'

Run 5 sacks of cement at 2950'

Mudded to 215'

Set rock bridge to 205'

Run 30 sacks of cement at 205'

Mudded to 40'

Set rock bridge to 35'

Run 15 sacks of cement to cap

Work started January 8, 1960

Work completed January 20, 1960

C. E. Shull Casing Pulling Company
Box 558
Great Bend, Kansas

License No. 8

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1960
CONSERVATION DIVISION
Wichita, Kansas