

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-009-15682-0000  
WELL PLUGGING RECORD

Barton County, Sec. 4 Twp. 16s Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner American Petrofina Company of Texas

Lease Name Polzin Well No. 1

Office Address Box 209 - Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed November 3 1937

Application for plugging filed February 26 1959

Application for plugging approved March 3 1959


Plugging commenced July 22 1959

Plugging completed July 29 1959

Reason for abandonment of well or producing formation Insufficient Production

If a producing well is abandoned, date of last production December 14 1958

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Donald Truan

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3216 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<del>3 1/2"</del>	204'	0
				7"	3308'	0
				5 1/2"	3316'	1099.75'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILLED HOLE WITH SAND FROM 3316-3200'

RUN 5 SACKS OF CEMENT AT 3200'

MUDDERED TO 200'

SET ROCK BRIDGE TO 185'

RUN 30 SACKS OF CEMENT AT 185'

MUDDERED TO 30'

SET ROCK BRIDGE TO 25'

RUN 15 SACKS OF CEMENT TO CAP.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C. E. Shull Casing Pulling Company

Address Box 558 Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
VERREL J. BRACK (employee of owner) ~~owner or operator~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Verrel J. Brack

BOX 209 RUSSELL, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of August, 1959

Carol Bennett  
Notary Public.

My commission expires 10-2-60

PLUGGING  
FILE SEC. 4 T. 16 R. 12W  
BOOK PAGE 18 LINE 38

RECEIVED  
STATE CORPORATION COMMISSION

AUG 7 1959

CONSERVATION DIVISION  
Wichita, Kansas

Brief Plugging Record on  
American Petrofina Co. of Texas's  
Polzin Well #1, in  
Barton County, Kansas

---

Total depth 3316'

7" casing set at 3308'

Cemented with 75 sacks

12 $\frac{1}{2}$ " casing set at 204'

Filled hole with sand from 3316' to 3200'

Run 5 sacks of cement at 3200'

Mudded to 200'

Set rock bridge to 185'

Run 30 sacks of cement at 185'

Mudded to 30'

Set rock bridge to 25'

Run 15 sacks of cement to cap

Work started July 22, 1959  
Work completed July 29, 1959

C. E. Shull Casing Pulling Company  
Box 558  
Great Bend, Kansas

License No. 8

