

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-19254-00-00

Spot: NESENE

Sec/Twnshp/Rge: 33-33S-11E

3485 feet from S Section Line,

611 feet from E Section Line

Lease Name: GRIFFITH

Well #: 1

County: CHAUTAUQUA

Total Vertical Depth: 1200 feet

Operator License No.: 33157

Op Name: R. D. ENERGY, INC.

Address: 905 N MONTGOMERY  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1200		50 SX
SURF	8.75	20		10 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug:

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: ROD DICKENS

Company:

Phone: (620) 725-3065

Proposed Plugging Method: Remove rods & tbg from well. Run 1" to 1150. Spot 20 sx cement at 1150. Perf casing at 650' and 350'. Run 1" & Spot 20 sx at 650'. Pull 1" to 350' and cement to surface. Cut off casing head and weld top plate.

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/12/2017 10:00 AM

KCC Agent: DUANE SIMS

4-24-17

**Actual Plugging Report:**

Perfs:

Ran 1" to 1143' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Next day ran back into 700' and spotted 22 sack plug. Pulled up to 350' and circulated cement to surface up backside of production casing. Pulled up to 200' and finished circulating cement to surface inside and outside of casing. Pulled 1" and topped well off. A total of 195 sacks of cement were used to plug this well. Well was cut off and location restored.

KCC WICHITA

APR 24 2017

RECEIVED

RECEIVED  
KCC DIST # 3

APR 19 2017

CHANUTE, KS


DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST SENT TO OPERATOR BY THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

INVOICED  
MAY - 3 2017

Form CP-2/3