

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-01943-00-00
Spot: NENENW Sec/Twnshp/Rge: 10-26S-18E
5163 feet from S Section Line, 3272 feet from E Section Line
Lease Name: FINNEY B Well #: 3
County: ALLEN Total Vertical Depth: 800 feet

Operator License No.: 33221
Op Name: ROXANNA PIPELINE, INC.
Address: 4600 GREENVILLE AVE STE 200
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	800		100 SX
SURF	6.25	20		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/22/2017 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: TOM GILBERT Company: _____ Phone: (785) 466-1158

Proposed Plugging Method: Connect pump truck directly to the casing and pump cement into well until it holds pressure.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 02/22/2017 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report: Ran 1" pipe down the inside of the 2.875" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe out of the casing. Ran 1" pipe down the backside of the 2.875" casing to 200'. Pumped and circulated cement through the 1" pipe on the backside of the 2.875" casing from 200' to surface. Pulled the 1" pipe. A total of 117 sacks of portland cement was reported used to plug this well.

Perfs: _____

RECEIVED
KCC DIST # 3
APR 19 2017
CHANUTE, KS

RD
4-24-17
KCC WICHITA
APR 24 2017
RECEIVED

Remarks: _____
Plugged through: TBG

District: 03 Signed [Signature]
(TECHNICIAN)

INVOICED
MAY - 3 2017
Form CP-2/3