

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-20422-00-02  
Spot: SENWNWSW Sec/Twnshp/Rge: 36-33S-20W  
1990 feet from S Section Line, 4630 feet from E Section Line  
Lease Name: BAKER Well #: 2  
County: COMANCHE Total Vertical Depth: 5080 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4374		WITH 10 SX CMT
PROD	5.5	6056	1528	WITH 350 SX CMT
SURF	8.625	653		WITH 300 SX CMT

Well Type: SWD UIC Docket No: D27949.0 Date/Time to Plug: 04/05/2017 2:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4374' WITH 2 SX CMT. PLUG AT 900' WITH 30 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/05/2017 6:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 4374' WITH 10 SX CMT. 1ST PLUG AT 900' WITH 30 SX CMT. 2ND PLUG AT 690' WITH 60 SX CMT. 3RD PLUG CIRCULATE CMT TO SURFACE FROM 200' WITH 55 SX CMT.

Top	Bot	Thru	Comments
4424	4430	CSG	

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL 2% CC BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

4-10-17

Signed [Signature]

(TECHNICIAN)

RECEIVED  
APR 10 2017  
KCC DODGE CITY

INVOICED

MAY - 3 2017

Form CP-2/3