

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-23344-00-00  
Spot: NWSWSENE Sec/Twnshp/Rge: 1-29S-14E  
2190 feet from N Section Line, 1040 feet from E Section Line  
Lease Name: DOCIA BATES Well #: 20  
County: WILSON Total Vertical Depth: 1116 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1100		112 SX
SURF	5	40		12 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2016 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Tie onto well and squeeze cement until pressure starts to rise and shut well in holding pressure. Bleed pressure off the next day and top well off using 15ppg portland cement.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 06/20/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The 2.875 inch casing was hooked onto directly and circulation established by pumping 4.5 bbls of water. The well was pumped full of cement containing cottonseed hulls and then shut in with 800 psi which held. A total of 42 sacks of portland cement were used to plug well.

Perfs:

RECEIVED  
KCC DIST # 3  
APR 19 2017  
CHANUTE, KS  
AD  
KCC WICHITA  
4-24-17 APR 24 2017  
RECEIVED

Remarks:  
Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)

INVOICED  
MAY - 8 2017