

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-23065-00-00  
Spot: NWSWNENE Sec/Twnshp/Rge: 1-29S-14E  
800 feet from N Section Line, 1200 feet from E Section Line  
Lease Name: DOCIA BATES Well #: 13  
County: WILSON Total Vertical Depth: 1109 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1104		116 SX
SURF	5	50		12 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/05/2016 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run 1" pipe to TD and pump 15ppg portland cement to surface than pull pipe and top well off.

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/05/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The 2.875 inch casing was hooked onto directly and circulation established. The well was pumped full of cement by squeezing and then shut in with 800 psi which held. A total of 36 sacks of portland cement were used to plug well.

Perfs:

RECEIVED  
KCC DIST # 3  
APR 19 2017  
CHANUTE, KS

AD

KCC WICHITA  
APR 24 2017

RECEIVED

Remarks:

Plugged through: CSG

4-24-17

District: 03

Signed Alan Dunning  
(TECHNICIAN)

INVOICED

MAY - 3 2017