

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-23067-00-00
Spot: NWNESWNE Sec/Twnshp/Rge: 1-29S-14E
1400 feet from N Section Line, 1740 feet from E Section Line
Lease Name: DOCIA BATES Well #: 15
County: WILSON Total Vertical Depth: 1100 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1090		109 SX
SURF	5	45		11 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2016 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run 1" pipe to TD of well and pump 15ppg portland cement to surface and trip pipe out then top well off.

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL
Date/Time Plugging Completed: 06/29/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The 2.875 inch casing was hooked onto directly and circulation established by pumping 4 bbls of water. The well was pumped full of cement containing cottonseed hulls by squeezing. The well was then shut in with 800 psi which held. A total of 66 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED
KCC DIST # 3
APR 19 2017
CHANUTE, KS

AD
KCC WICHITA
APR 24 2017
RECEIVED

4-24-17

Remarks:
Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)

INVOICED
MAY - 3 2017