

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-23539-00-00  
Spot: SESESWNE Sec/Twnshp/Rge: 1-29S-14E  
2475 feet from N Section Line, 1635 feet from E Section Line  
Lease Name: DOCIA BATES Well #: 27  
County: WILSON Total Vertical Depth: 1127 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1115		131 SX
SURF	5	40		11 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2016 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST D SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Hook up to well and pump 15 ppg portland cement until well pressures up. Shut well in and return the next day to bleed pressure and top well off. Well will then be cut below plow depth.

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/21/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was run to 1015 ft. The well was pumped full of cement thru the one inch pipe. Approx 1/2 the cement string was removed and the well pumped full again. The remaining one inch was removed and the well topped off with cement. A total of 33 sacks of portland cement were used to plug well.

Perfs:

RECEIVED  
KCC DIST # 3  
APR 19 2017  
CHANUTE, KS

AD

KCC WICHITA  
APR 24 2017

RECEIVED

4-24-17

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)

INVOICED

MAY - 3 2017