

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-23345-00-00
Spot: SENWSENE Sec/Twnshp/Rge: 1-29S-14E
1840 feet from N Section Line, 850 feet from E Section Line
Lease Name: DOCIA BATES Well #: 21
County: WILSON Total Vertical Depth: 1103 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1095		106 SX
SURF	5	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2016 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST D SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Tie onto well and squeeze cement until pressure starts to rise and shut well in holding pressure. Bleed pressure off the next day and top well off using 15ppg portland cement.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 06/20/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The 2.875 inch cement string was hooked onto directly and circulation established by pumping 4 bbls of water. The well was pumped full of cement containing cottonseed hulls by squeezing. The well was then shut in with 800 psi which held. A total of 32 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
KCC DIST #3
APR 19 2017
CHANUTE, KS
AD
KCC WICHITA
4-24-17 APR 24 2017
RECEIVED

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)

INVOICED
MAY - 3 2017