

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-23540-00-00
Spot: SWSWSENE Sec/Twnshp/Rge: 1-29S-14E
2475 feet from N Section Line, 1285 feet from E Section Line
Lease Name: DOCIA BATES Well #: 28
County: WILSON Total Vertical Depth: 1110 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1107		119 SX
SURF	5	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2016 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST D SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Hook up to well and pump 15 ppg portland cement until well pressures up. Shut well in and return the next day to bleed pressure and top well off. Well will then be cut below plow depth.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 06/20/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report: The 2.875 inch casing was hooked onto directly and circulation established by pumping 4 bbls of water. The well was pumped full of cement containing cottonseed hulls by squeezing. The well was then shut in with 800 psi which held. A total of 39 sacks of portland cement were used to plug well.

Perfs: _____
RECEIVED
KCC DIST #3
APR 19 2017
CHANUTE, KS
AD
KCC WICHITA
APR 24 2017
RECEIVED

Remarks: _____
Plugged through: CSG

4-24-17

District: 03 Signed Alan Dunning
(TECHNICIAN)

INVOICED
MAY - 3 2017