

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-22950-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 1-29S-14E
1640 feet from N Section Line, 1465 feet from E Section Line
Lease Name: DOCIA BATES Well #: 12
County: WILSON Total Vertical Depth: 1095 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1074		106 SX
SURF	5	50		11 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2016 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Revd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run 1" to TD of well and pump 15 ppg portland cement to surface than trip out and top well off.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 12/02/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

12-1-2016: A one inch cement string was lowered to 500 ft and encountered resistance. The cement string was then washed to 625 ft. Cement was then pumped but did not return to surface. Pulled one inch cement string; will tag cement tomorrow. 12-2-2016: Ran cement string to 225 ft where the cement was tagged. The well was then pumped full of cement. A total of 168 sacks of of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED
KCC DIST # 3
APR 19 2017
CHANUTE, KS
AD
KCC WICHITA
APR 24 2017
RECEIVED

4-24-17

Remarks:
Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)

INVOICED
MAY - 3 2017