

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-25041-00-00
Spot: SWNWSWNW Sec/Twnshp/Rge: 7-29S-15E
1815 feet from N Section Line, 165 feet from W Section Line
Lease Name: TIMMONS GN Well #: 1
County: WILSON Total Vertical Depth: 1137 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	1137		136 SX
SURF	6.25	20		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2016 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run one inch pipe to TD of hole and pump cement to surface than trip out and top well off. Cut well below plow depth and cover.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 09/12/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report: The wellhead was directly connected to and circulation established by pumping 5.5 bbls of water. The well was pumped full of cement containing cottonseed hulls by squeezing. The well was then shut in with 750 psi which held. A total of 39 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs: _____
RECEIVED
KCC DIST #3
APR 19 2017
CHANUTE, KS
IAD
KCC WICHITA
APR 24 2017
RECEIVED
4-24-17

Remarks:
Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)

INVOICED
MAY - 3 2017