

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-19665-00-00  
Spot: SWNENENW Sec/Twnshp/Rge: 6-29S-15E  
610 feet from N Section Line, 2130 feet from W Section Line  
Lease Name: MARTIN NICKEL Well #: 3  
County: WILSON Total Vertical Depth: 1130 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1126		134 SX
SURF	5	40		12 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2016 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST D SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Hook up to well and pump 15 ppg portland cement until well pressures up. Shut well in and return the next day to bleed pressure and top well off. Well will then be cut below plow depth.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 07/11/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The wellhead was connected to and circulation established by pumping 3 bbls of water. The well was pumped full of cement by squeezing. The well was then shut in with 800 psi which held. A total of 49 sacks of portland cement were used to plug well. The wellhead was cut off below plow depth and the location restored.

Perfs:

RECEIVED  
KCC DIST # 3  
APR 19 2017  
CHANUTE, KS

AD

KCC WICHITA  
APR 24 2017  
RECEIVED

4-24-17

Remarks:

Plugged through: CSG

District: 03

Signed Alan by. Dunning  
(TECHNICIAN)

INVOICED

MAY - 3 2017