

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-19664-00-00  
Spot: NESENEW Sec/Twnshp/Rge: 6-29S-15E  
720 feet from N Section Line, 2370 feet from W Section Line  
Lease Name: MARTIN NICKEL Well #: 2  
County: WILSON Total Vertical Depth: 1175 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1167		139 SX
SURF	5	40		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2016 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST D SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Hook up to well and pump 15 ppg portland cement until well pressures up. Shut well in and return the next day to bleed pressure and top well off. Well will then be cut below plow depth.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 11/04/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was run inside the two inch production pipe to 1015 ft. A one inch cement string was also run outside the two inch production pipe to 860 ft. The well was then pumped full of cement thru the cement strings. A total of 212 sacks of portland cement were used to plug well. The wellhead was cut off below plow depth and the location restored.

Perfs:

KCC WICHITA  
APR 24 2017  
RECEIVED

4-24-17

RECEIVED  
KCC DIST # 3  
APR 19 2017  
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning  
(TECHNICIAN)

INVOICED

MAY - 9 2017