

*Rec'd 12-14-83*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21,899-0000 ✓

E/2 SE SW, Sec. 4, T 22 S, R 13 W/4

660 feet from N/S section line

2310 feet from W/E section line

*R*

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Mueller Well # 1-4

Operator: Texas Energies Inc  
Name & Address P.O. Box 947  
Pratt, Kansas  
67124

County Stafford

Well Total Depth 3880 feet <sup>\$</sup>126.10

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Oilfield Serv. License Number 5149

Address P.O. Box 329 Pratt, Kansas 67124

Company to plug at: Hour: 4:00pm Day: 11 Month: December Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Greg Bailey

(company name) Wheatstate Oilfield Service (phone) \_\_\_\_\_

were: To use 60/40 pozmix, 2% gel 3% cc

1st plug @ 3800' w/50sx, 2nd plug @ 1170'

w/50'sx, 3rd plug @ 420' w/50'sx, 4th plug

@ 40' w/solid Bridge plug + 10'sx, Circulate

15'sx in the Rathole, Put 5'sx in the waterwell

Signed Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:00pm Day: 11 Month: December Year: 19 83

ACTUAL PLUGGING REPORT Plugged as proposed in the above paragraph  
Halliburton pumped the cement

Remarks: \_\_\_\_\_

I hereby certify that the above plugging instructions were given as herein stated  
and that I ~~did~~ / did not observe this plugging.

**INVOICED**

Signed Richard W. Lacey ✓  
(TECHNICIAN)

DATE 1-11-84

INV. NO. 9005 W