

1050548

Revised 6-11-85

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION ^{100'} S NW SW NW SEC. 4, T22 S, R13 ~~W22~~
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,228-0000
3530 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Chase Well Well # 1

Operator: L.D. Drilling, Inc

County Stafford *122.82*

Name & Address R.R. 1 Box 183 B

Well Total Depth 3779 (Arbuckle) feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 310'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling Inc. License Number 6039

Address Same as above

Company to plug at: Hour: 2:00 pm Day: 4 Month: June Year: 19 85

Plugging proposal received from Don Popp

(company name) L.D. Drilling (phone) 316-793-3051

Notes: Keep hole full of good quality drilling mud and spot all plugs through open ended drill pipe. 1st plug at 780' with 50 sacks of cement. 2nd plug at 360' with 40 sacks of cement. 3rd plug at 40' with a solid bridge built of 1 sack of hulls and 8 5/8" wiper plug. and fill hole on up with 10 sacks of cement. Use 60/40 pozmix 2% gel 3% cc for cement. The Anhydrite was at 767' to 774' Circulate rat hole with 15 sacks of cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:15 pm Day: 4 Month: June Year: 19 85

ACTUAL PLUGGING REPORT Kept hole full of good heavy drilling mud and spotted all plugs through open ended drill pipe. 1st plug at 780' with 50 sacks of cement. 2nd plug at 360' with 40 sacks of cement. 3rd plug at 40' with a solid bridge plug built of 1 sack hulls and a 8 5/8" wiper plug. Filled hole to surface with 10 sacks of cement. Circulated rat hole with 15 sacks of cement. Halliburton pumped the cement which was 60/40 pozmix 2% gel 3% cc cement

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE 6-18-85

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 8542