

To: 1052230

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

NWNE NW, SEC. 3, T 22 S, R 13 W

RECEIVED 4950 feet from S section line  
KANSAS CORP 3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893 3-13-98  
Lease Name Gates Well # A-5

Operator: Pratt Well Service Inc. County Stafford 123.18

Name & Address P.O. Box 847  
Well Total Depth 3790' feet

Pratt, KS. 67124-0847  
Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 250

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt well Service Inc. License Number 5893

Address P.O. Box 847 Pratt, KS 67124-0847

Company to plug at: Hour: 8:30am Day: 5 Month: March Year: 1998

Plugging proposal received from Kenneth Gates

(company name) Pratt Well Service (phone) 316-672-5901

work: Pump 50 sx of cement through the perms. Pull tubing

to 750' and circulate cement to surface

CIBP set at 3623

5 1/2" casing was squeezed at 240' with 200sx

cement. Perforations 3421-26 3476-90

3494-3497 3513-19 3535-3531 Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30pm Day: 5 Month: March Year: 1998

ACTUAL PLUGGING REPORT Ran tubing to 3562 and spotted 1sx Hulls

# 25sx cement. WOC 2 hrs Ran tubing to 3246

and spotted 1sx Hulls # 25sx cement. (good circulation)

Pulled tubing to 752'. Pumped 58 sx of cement,

circulating cement to surface. Pulled tubing and

topped well off with 2sx cement

Remarks: Halliburton pumped 60/40 poz mix 6% gel.

INVOICED (additional description is necessary, use BACK of this form.)  
DATE MAR 23 1998 observe this plugging.

INV. NO. 50286 Signed Richard W. Lucy (TECHNICIAN)  
3-5 FORM CP-2/3