

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 15-185-12767-0000

LOCATION NE SE SE

SEC. 33 TWP. 23 RGE. 13

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Clair Box 169

Operator Crown Oil Co Address Great Bend, Kans

Field St Johns T.S. County Stafford

Total Depth 3930 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 320' circulated with cement. 5 1/2" at 3934 with
100 sax cement behind. Lane Wells plugs to 3790', top perf
3752'.

Filled with chat to 3730', set 5 sax cement with dump bailer,
pulled 3200' 5 1/2", filled hole with mud to 320', set rock
bridge and 15 sax cement, filled with mud to 30', set rock
and 10 sax cement to bottom cellar.

J. P. ...

5-10-51

District Conservation Agent

RECEIVED

Date 5-5-51 STATE CORPORATION COMMISSION

MAY 10 1951

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
SEC 33 T 23 R 13
BOOK PAGE 80 LINE 49