

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 15-185-11468-0000

LOCATION N2E 2W-3E

SEC. 23 TWP. 23 RGE. 13-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Rising

Operator Crown Oil Co. Inc. Address St. Bend - Kansas

Field _____ County Stafford

Total Depth 3980 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 356 ft - Circulated with cement.
5 1/2" casing set at 3980 ft - Tool Wells Plug at 3921 ft -
Filled with chat to 3625 ft - Dumped 15 sacks of
Cement at 3625 ft - Shot off & Pulled the 5 1/2" casing -
Filled with mud to 356 ft - Set Rock Bridge &
25 sacks of cement at 356 ft - Mud to 30 ft -
Bridge & 10 sacks of cement at the
Surface -

RECEIVED

Conservation-Div.

6-17-50

JUN 17 1950

C. W. Stouck
District Conservation Agent

PLUGGING STATE CORPORATION
FILE SEC 33 T 23 R 130 COMMISSION
BOOK PAGE 11 LINE 29 KANSAS

Date 6-14-50

X