

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-185-12766-0000 of this well)

Operator's Full Name Southern States Oil Co.

Complete Address Box 1365- Great Bend, Ks. 67530

Lease Name Williams "A" Well No. 7

Location SW NW SW Sec 32 Twp. 23S Rge. 13 (E) (W) X

County Stafford Total Depth 3679

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176- Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12 N Day 27 Month 4 Year 1979

The above well was plugged as follows:

168' 8 5/8" casing w/125 sax cement. 5 1/2" casing set @ 3666' w/100
sax cement. Open hole. Sand back to 3640'- Top sand w/5 sax mixed cement
w/ dump bailer. Pull 2930' 5 1/2" casing. Allied mixed & pumped 5 sax
hulls- 25 sax gel, release plug, mixed & pumped 125 sax 50/50 posmix
cement w/2% gel & 3%cc to top of casing. Shut in w/200# pressure.

STATE CORPORATION COMMISSION

MAY - 1 1979 5-1-79

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5-2-79
INV. NO. 9551-W