

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 19 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name W. R. Gross 15-185-10955-0000

Complete Address: Box 510, El Dorado, Kansas

Lease Name Williams Well No. # 5

Location SW NE SW Sec. 32 Twp. 23 Rge. 13 (E) (W)

County Stafford Total Depth 3673'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 12:30 PM Day 16th Month Dec. Year 1966

The Above well was plugged as follows:

325' of 8 5/8" surface pipe, cement circulated. 3667' of 5 1/2" long string,  
no record on cement. Top perforation 3300'. Bottom of the hole was sanded  
to 3290', and cemented with 5 sacks, through the dump bailer. 1500' of 5 1/2"  
long string was recovered from the hole. Bridge plug was pushed in fluid to  
300', bridge plug and rock bridge from 300' to 290'. 5 sacks of cement was  
mixed in a barrel, and put on plug at 290', through the dump bailer, and let  
set over-night. Next day hole was bailed dry, and 20 sacks of cement was added  
to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30',  
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12/19/66

INV. NO. 4470-11