



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name C. K. Edmiston

Complete Address: 435 1st Hall Bank Bldg Wichita Kans.

Lease Name Drach Well No. -1-

Location SW-SE Sec. 11 Twp. 22 Rge. 13 (E) (W) K

County Stafford Total Depth 3752

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: South West Casing Pulling Co.

Address: 364 West Bend Kans License No. 399

Operation Completed: Hour 1:00 Day 24 Month 10 Year 68

The Above well was plugged as follows:

259' 8 3/4" surface pipe circulated with cement, 3752' - 5 1/2" pipe
sand to 3370' and 5 sacks cement, pumped 5 sacks Gal
mud down 600' up to and 40 sacks cement up to 470'
then 8 sacks Gal mud and 25 sacks cement up to
40' and 10 sacks to surface.
Recovered 1810' 5 1/2" in pipe

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10/28/68
INV. NO. 8918-11