

15.185.13205.0000

Form CP-3  
Rev. 6-26-62

*4*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued January 30, 1967

RECEIVED  
CONSERVATION COMMISSION  
FEB 14 1967  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Kansas

Lease Name Sittner Well No. # 2

Location NE SE SW Sec. 11 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3765'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 12:30PM Day 13th Month Feb. Year 1967

The Above well was plugged as follows:

274' of 8 5/8" surface pipe, cemented with 250 sacks. 3748' of 5 1/2" long  
string, cemented with 150 sacks. Top perferation 3436'. Bottom of the hole  
was sanded to 3400', and cemented with 5 sacks, through the dump bailer.  
2505' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed  
in fluid to 260', bridge plug and rock bridge from 260' to 250'. 4 sacks of  
cement was mixed in a barrel, and put on plug at 250', through the dump  
bailer, and let set over-night. Next day hole was bailed dry, and filled with  
3 yards of ready-mix cement from 235' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 2/14/67  
INV. NO. 4757-W