

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

APR 27 1964
4-27-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Woody's Quality Oil Company

Complete Address: 1119 Cravens Bldg., Oklahoma City, Oklahoma

Lease Name Soeken "A" Well No. # 3

Location SW NE SE Sec. 10 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3880

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Tommy Ward Drilling Company

Address: 609 Liberty Bank Bldg., Oklahoma City, Okla. License No.

Operation Completed: Hour 6:30AM Day 25th Month April Year 1964

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated. Fluid was up in the
hole. 1st cementing plug and 1/2 sack hulls was pushed to 245', and cem-
ented with 25 sacks, through the drill pipe. Hole was filled with drill-
ing mud to 40', 2nd cementing plug, bridged with hulls, and cemented
with 10 sacks to base of the cellar. Rat and mouse hole bridged and
cemented with 5 sacks.

This cementing was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/28/64
INV. NO. 9043-W

Signed: Archie Elving
Well Plugging Supervisor