

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1967

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Well Plugging Authority,
issued July 7, 1967.

Operator's Full Name Sooner Pipe & Supply Corporation

Complete Address 301 Petroleum Club Bldg., Tulsa Oklahoma 74119

Lease Name Soeken Well No. # A-1

Location SE NE SE Sec. 10 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 11:15 A.M. Day 4th Month August Year 1967

The above well was plugged as follows:

207' of 8 5/8" surface pipe, cemented with 250 sacks. 3850' of 4 1/2" long string, cemented with 100 sacks. Plug back T.D. 3819'. No record of any perforations. Bottom of the hole was sanded to 3650', and cemented with 4 sacks, through the dump bailer, with cement from 3650' to 3600'. 3105' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 205', bridge plug and rock bridge from 205' to 195'. 3 sacks of cement was mixed in a barrel, and put on plug at 195', through the dump bailer, and let set over-night. Next day hole was bailed dry, and hole was filled with 2 3/4 yards of ready-mix cement, with cement from 195' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 8/8/67INV. NO. 6091-22