

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1966
11-23-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas

Lease Name Boileau Well No. # 1

Location SW NW SW Sec. 10 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3852'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:15PM Day 21st Month Nov. Year 1966

The Above well was plugged as follows:

294' of 8 5/8" surface pipe, cemented with 235 sacks. 3851' of 5 1/2" long string, cemented with 150 sacks. Plug back T.D. 3835'. Top perforation 3551'. Bottom of the hole was sanded to 3500', and cemented with 5 sacks, through the dump bailer. Hole was flowing and a squeeze job was necessary. 10 sacks of Gel-Mud and 75 sacks of cement was pumped in the surface pipe, through an 8 5/8" swage, to a pressure of 250 lbs., with cement to the base of the cellar. A plug was run ahead of the Gel-Mud. This cement was pumped by Forbes Casing Pulling, Inc. 2820' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/29/66
INV. NO. 4334-W