

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION 21w-21w-SE

SEC. 10 TWP. 22 RGE. 13-w

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Sachsen

Operator Cyan Oil Co Address A. Bend - Kans -

Field \_\_\_\_\_ County Stafford

Total Depth 3815' Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 304 ft. Circulated with cement.  
1 1/2" casing set at 3815 ft. Cemented with 100 sacks of  
cement. Plugged back to 3770 ft with chat  
dumped 5 sacks of cement at 3770 ft. Shot off &  
pulled the 5/8" string - mud to 306 ft. Set Rock  
Bridges & 15 sacks of cement at 306 ft. Mud to 29 ft  
Plug & 10 sacks cement at the surface -

APR 16 1951  
CONSERVATION DIVISION  
WICHITA, KANSAS  
C. H. Stovish  
District Conservation Agent

4-16-51

Date 4-13-51

**PLUGGING**  
FILE SEC 10 TWP 22 R 13w  
BOOK PAGE 79 LINE 5