

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1966

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasOperator's Full Name Tom-Kat, Inc.Complete Address: 1127 Wichita Plaza, Wichita, KansasLease Name Hullman Well No. # 2Location SE SE NW Sec. 10 Twp. 22 Rge. 13 (E) (W) WCounty Stafford Total Depth 4150'Abandoned Oil Well Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Lost HolePlugging Contractor: Tom-Kat, Inc.Address: 1127 Wichita Plaza, Wichita, Kansas License No. Operation Completed: Hour 1:45PM Day 3rd Month June Year 1966

The Above well was plugged as follows:

288' of 10 3/4" surface pipe, cement circulated with 250 sacks. 3835' of
7" long string, cemented with 100 sacks. Pipe had collapsed at 2600', and
no tools had been in the hole to drill out the bottom cement. 1200' of 7"
long string was recovered from the hole. Fluid level in the hole was at
100'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 260',
and cemented with 25 sacks, through the drill pipe. Hole was filled with
drilling mud to 30', bridged with 1/2 sack of hulls on fluid at 30', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged and
cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 6/13/66
INV. NO. 3396-u