



KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name National Cooperative Refinery Association

Complete Address: 305 Rule Bldg., Wichita, Kansas

Lease Name Curtis "B" Well No. # 3

Location C NW NW Sec. 6 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3610

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 11:30AM Day 30th Month Sept. Year 1963

The Above well was plugged as follows:

343' of 8 5/8" surface pipe, cemented with 250 sacks. 3609' of 5 1/2" long
string, cemented with 125 sacks. Plugged back to 3300', with a Baker plug,
Top of plug was cemented with 2 sacks. Fluid level was up in the hole.
6 sacks cement was mixed in barrel, and put on plug with dump bailer.
Plug was set at 300', with 10' rock bridge. This was left to set over
night. Next morning hole was bailed down, and 19 sacks cement was added
to plug, at 300', Hole was filled with mud to 40', 10' rock bridge,
cemented with 10 sacks to base cellar. 2990' of 5 1/2" long string was re-
covered from the hole

I hereby certify that the above well was plugged as hersin stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10-1-63

INV. NO. 7826 W