

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 6 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued March 24, 1967.

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address: P. O. Box 6, Great Bend, Kansas

Lease Name Curtis "B" Well No. 2

Location W/2 NW NW Sec. 6 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3740'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 11:30AM Day 3rd Month April Year 1967

The Above well was plugged as follows:

341' of 8 5/8" surface pipe, cemented with 250 sacks. 3734' of 5 1/2" long
string, cemented with 225 sacks. Plug back T.D. 3550'. Top perferation 3504'.
Bottom of the hole was sanded to 3490', and cemented with 5 sacks, through
the dump bailer. 2498' of 5 1/2" long string was recovered from the hole. Bridge
plug was pushed in fluid to 300', bridge plug and rock bridge from 300' to
290'. 6 sacks of cement was mixed in a barrel, and put on plug at 290',
through the dump bailer, and let set over week-end. Hole was bailed dry and
filled with 4 yards of ready-mix cement from 270' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/6/67

INV. NO. 5008-W