

DISTRICT CONSERVATION AGENT'S REPORT

15-009-00221

0000

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 4-9

LOCATION NW-NW-SW

SEC. 4 TWP. 16 RGE. 12 W

Dry Hole          Abandoned Oil Well   ✓   Abandoned Gas Well         

I have this date completed supervision of plugging of:

Well No. 1 Lease Polgine

Operator Fleming & Woodman Address Heisington Kansas

Field          County Barton

Total Depth 3331 1/2 Feet.

Plugging Contractor Miller Casing Pulling Co

Plugging Contractor's License No. 12

Address Great Bend Kansas

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" 145' C.W.C. Oil String 5 1/2" @ 3329'  
W/ 100 SX Cem. Top Ref 3331. Fill back with sand  
to 3300' and dump 5 SX Cem. Shoot off and pull  
5 1/2" casing mud to 200' set rock bridge and  
mix and run 30 SX of Cem. mud to 35' rock  
bridge and 10 SX of mixed Cem. to surface.

**PLUGGING**  
FILE SEC 4 TWP 16 R 12W  
BOOK PAGE 7 LINE 9

01-11-54

Warren H. Horner  
District Conservation Agent

Date 1-8-54