

DISTRICT CONSERVATION AGENT'S REPORT

*[Handwritten signature]*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

15-009-19310-0000

FILE NO. 146-5

LOCATION 566-522-541

SEC. 4 TWP. 16 RGE. 12

Dry-Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Peterson

Operator Mr. Earl F. Wakefield Address 306-7 N. Hill Road, Wichita, Kan.

Field \_\_\_\_\_ County Barton

Total Depth 3266 Feet.

(Describe briefly the manner in which the well was plugged)

Cable Tool Hole - All Pipe Pulled out of hole except  
the 12 1/2 - 480 ft. it was circulated with cement.  
Filled hole with heavy mud as the pipe was pulled.  
Set Rock Bridge & 25 sacks of cement at 875 ft.  
Rock Bridge & 25 sacks of cement at 500 ft.  
Rock Bridge & 10 sacks of cement at the surface.  
Heavy mud between all cement plugs.  
Earl Wakefield - Plugging Contractor

*end*  
*04-13-50*

**PLUGGING**  
FILE SEC. 4-16-1950  
BOOK PAGE 46 LINE 5

C. M. Stough  
District Conservation Agent

Date 4-10-50