

KCC OIL/GAS REGULATORY OFFICES

Date: 4/27/18

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 30742

API Well Number: 15-135-25992-00-00

Op Name: Palomino Petroleum, Inc.

Spot: SW-NW-NW-NE Sec 11 Twp 20 S Rng 22 E / W

Address 1: 4924 SE 84th St.

4735 Feet from N / S Line of Section

Address 2: _____

2476 Feet from E / W Line of Section

City: Newton

GPS: Lat: 38.33305 Long: 99.72251 Date: 4/27/18

State: KS Zip Code: 67114 -8827

Lease Name: Uehling-Schwein Well #: 1

Operator Phone #: (316) 799-1000

County: Ness

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Glenn Dinkel.

Findings:

TD-4545'.
 8 5/8" set @ 218' w/150 sx cement (circulated).
 5 1/2" set @ 4544' w/170 sx cement on the primary cementing job (2/21/18).
 Swift had to work on their pump truck controls.
 Company opened the port collar @ 1475'.
 Swift Services, Inc. pumped 100 bbl mud to condition the hole, then 100 sx SMD cement, with little or no returns. Shut down for 30 minutes, then pumped the remaining 100 sx, with intermittent returns. Waited on more cement. A bulk truck loaded with 60/40 poz, 4% gel returned. Pumped 200 sx 60/40 poz, 4% gel, circulating 15 sx to the pit. Closed the port collar.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: On-site witness
- KGS
- District Files
- TA Program
- Courthouse

By: Eric MacLaren

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

KCC DODGE CITY

Form: _____

RECEIVED
 MAY 7 2018