

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

070102 - Habiger-Krampe.pdf

Form T-  
June 2000

Form must be Type:  
Form must be Signed:  
All blanks must be Filled:

REQUEST FOR CHANGE OF OPERATOR  
TRANSFER OF INJECTION OR SURFACE POND PERMIT  
RECEIVED

July 1, 2002

Check Applicable Boxes:

☒ Oil Lease: No. of Wells 1

☐ Gas Lease: No. of Wells 1

\*\* Side Two Must Be Completed.

☐ Saltwater Disposal Well - Docket No.                     

Spot Location:                      feet from N / S Line

                     feet from E / W Line

☐ Enhanced Recovery Project Docket No. E-19,665

Entire Project: ☐ Yes ☐ No #2 INJ. WAS P4A 12-11-97

Number of Injection Wells 1 DOCKET CANCELED

Field Name:                     

Effective Date of Transfer:                     

MAR 26 2003

KCC WICHITA

Lease Name: Habiger-Krampe

SE/4 Sec. 8 Twp. 18 R. 10W ☐ E ☐ W

Legal Description of Lease:                     

above SE/4

County: RICE

Production Zone(s): Lansing- KC & Arbuckle

Injection Zone(s):                     

Surface Pond Permit #                     

(API # if Drill Pit)

                     feet from N / S Line of Section

                     feet from E / W Line of Section

Identify: ☐ Emergency Pit ☐ Burn Pit ☐ Storage Pit ☐ Drill Pit

Past Operator's License No. 5088

Past Operator's Name & Address: John J. Darrah, Jr.

225 N. Market # 300 Wichita, KS 67202

Title:                      Agent

Contact Person: G.P. Stoeppelwerth

Phone: 316-263-2243

Date: November 22, 2002

Signature: [Signature]

New Operator's License No. 3134

New Operator's Name & Address: Terry E. Morris/GLM Co.

P.O. Box 193, Russell, KS 67665-0193

Title: OWNER

Contact Person: TERRY E. MORRIS

Phone: (785)483-2123

Oil / Gas Purchaser: NCRA

Date: December 10, 2002

Signature: Terry E. Morris

**Acknowledgment of Transfer:** The above request for transfer of injection authorization, surface pond permit #                      has been noted, approved and duly recorded in the records of the Kansas Corporation Commission. This acknowledgment of transfer pertains to Kansas Corporation Commission records only and does not convey any ownership interest in the above injection well(s) or pond permit.

                     is acknowledged as the new operator and may continue to inject fluids as authorized by

Docket #                      Recommended action:                     

Date:                     

Authorized Signature

                     is acknowledged as the new operator of the above named lease containing the surface pond

permitted by #                     

Date:                     

Authorized Signature

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

3/28/03 JUN 20 2003 4/03

MUST BE FILED FOR ALL WELLS

*LEASE NAME	API NO.	LOCATION	FOOTAGE FROM SECTION LINE (i.e. FSL Feet from South Line)	TYPE OF WELL (OIL/GAS INJ/WSW)	WELL STATUS (PROD/TA'D ABANDONED)
1	drld 1971	990 ft from SOUTH LINE	2310 ft from EAST Line	OIL	ABND
2	<u>E-19665</u>	330 ft from SOUTH LINE	330 ft from EAST Line	INJ	ABND
3	159-20893	330 ft from SOUTH LINE	1650 ft from EAST Line	OIL	ABND
4	159-01471	2310 ft from SOUTH LINE	990 ft from EAST Line	OIL	ABND
5	<u>15-159-00644</u> OWMO-1980 ✓	2310 ft from SOUTH LINE	2310 ft from EAST Line	OIL	TA
6	159-21234	330 ft from SOUTH LINE	330 ft from EAST Line	OIL	ABND
		ft from SOUTH LINE	ft from EAST Line	OIL	PROD

A SEPARATE SHEET MAY BE ATTACHED IF NECESSARY

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

12-11

API NUMBER: 15-159-20,772

SE SE SE, SECTION 8 TOWNSHIP 18 RANGE 10W

OPERATOR LICENSE # 5088 330 FEET FROM S SECTION LINE  
OPERATOR JOHN LAY DARRAH JR. 330 FEET FROM E SECTION LINE  
NAME & 225 N MARKET, STE #300  
ADDRESS WICHITA, KS 67202

LEASE NAME: HABIGER - KRAMPE #2

COUNTY: RICE

WELL TOTAL DEPTH: 3270 106.28

PIPE: 5 1/2 - 3270

SURFACE CASING: 8 5/8 - 260'

ABANDONED OIL WELL GAS WELL INPUT WELL X SWD D&amp;A

OTHER WELL AS HEREBINAFTER INDICATED:

PLUGGING CONTRACTOR: D.S. &amp; W. WELL SERVICING, INC.

ADDRESS: CLAFILIN, KS 67525

LICENSE: 6901

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 11 MONTH: 12 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: KENT STRUBE

COMPANY NAME: D.S. &amp; W. WELL SERVICING, INC.

PHONE: 316-587-3361

WERE: 30 SKS ON BOTTOM

35 SKS 1200

35 SKS 850

310 TO 0

PLUGGING PROPOSAL RECEIVED BY: P.W.

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART ( ) NONE ( )

COMPLETED: HOUR: 2:30 DAY: 11 MONTH: 12 YEAR: 1997

ACTUAL PLUGGING REPORT: TUBING WAS STUCK IN HOLE. SHOT IT OFF AT 2003' PULLED SHORT

SUB. PUMPED 50 SKS CEMENT, CIRCULATED TO SURFACE. CIR HOLE CLEAN WITH FRESH WATER.

PULLED TUBING AND TAGED CEMENT AT 2300'. SHOT 5 1/2" CASING OFF AT 1400'. PULLED

TO 1200'. PUMPED 35 SKS PULLED TO 850'. PUMPED 35 SKS PULLED TO 310'

CIRCULATED CEMENT TO SURFACE.

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 23 1997

REMARKS: ALLIED #4491 60/40 4%

CONSERVATION DIVISION  
WICHITA, KS

I DID NOT OBSERVE THIS PLUGGING.

*Jack H. Smith*  
\*\*\*NAME\*\*\*

INVOICED

DATE JAN 05 1998

INV. NO. 49819

12-11

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
60 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-20772

LEASE NAME Habiger-Krampe

WELL NUMBER #2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 8 TWP. 18 SRGE. 10 (E) or (W)

COUNTY Rice

Date Well Completed \_\_\_\_\_

Plugging Commenced 12-05-97

Plugging Completed 12-10-97

EASE OPERATOR John Jay Darrah Jr.

ADDRESS 225 N. Market Suite 300 Wichita, KS 67202-3417

PHONE 816 263-2243 OPERATORS LICENSE NO. 5088

Character of Well \_\_\_\_\_

Oil, Gas, O&A, SWD, Input, Water Supply Well

When plugging proposal was approved on 12-10-97

(date)

by Richard Lacey

(XCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 3001 Bottom 3184 T.D. 3270

Now depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content Surface	From	To	Size	Put in	Pulled out
		0	260'	8 5/8"	260'	0
	Production	0	3270'	5 1/2"	3270'	1409'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Allied mixed 50 sacks common, displaced with 7 bbls. fresh water, cement circulated to surface. Waited on backhoe to dig pit, washed out cement to pit with 30 bbls. of water, had holes in tubing. Loaded hole, mixed 35 sacks @ 1250', 35 sacks @ 850'. Pulled casing to 310' and circulated cement to surface with 130 sacks. Pulled casing and hole stayed full. Minimum pressure was 100# and maximum pressure was 250#. 10:30 am 12:00 pm

Name of Plugging Contractor D S & W Well Servicing, Inc.

License No. 6901

Address P.O. Box 231 Claflin, KS 67525

STATE OF KANSAS COMMISSION

Name of Party Responsible for Plugging Fees: John Jay Darrah Jr.

JAN 8 1998

State of Kansas

County of Barton

SS. PUBLIC NOTARY

Arthur P. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arthur P. Strube

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 98

My Commission Expires: April 8, 2001

