

* CORRECTION *

KOLAR DOCUMENT ID: 100140

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1661401

WELL ID

✓ Original Record ☐ Correction ☐ Change in Well Use

LOCATION OF WATER WELL

Latitude	37.707656	Longitude	-100.11753	Section	13	Township	27	Range	26	☐ E ☒ W	Fraction	NE ¼ NE ¼ NW ¼
Datum	WGS84	Elevation	2602	County	Ford							

WATER WELL OWNER

Name	Mitchell Shelton
Business	
Address	10537 Outlaw Rd Dodge City KS 67801
Well location	
✓ at owner's address	

WELL WATER USE

Domestic Household

COMPLETION

Depth of completed well:	380 ft.
Depth(s) groundwater encountered:	
(1) 150 ft.; (2) 220 ft.;	
(3) _____ ft.; (4) ☐ dry well	
Static water level in well:	280 ft. 190'
✓ measured below land surface on (mm/dd/yy):	08/17/2022
☐ measured above land surface on (mm/dd/yy):	

NEAREST SOURCE OF POTENTIAL CONTAMINATION

Source:	
Distance from well:	Direction from well:
Source description:	
Source:	
Distance from well:	Direction from well:
Source description:	
✓ No potential source of contamination within 100 feet.	

CONSTRUCTION

Borehole interval:	Borehole diameter:
from 0 to 380 ft.	10 in.
from _____ to _____ ft.	_____ in.
Casing height above land surface:	18 in.
If casing height is less than 12 in. has a variance been approved?*	☐ Yes ✓ No
*variance not required for monitoring or environmental remediation wells	
Casing type:	ThermalPlastic
Blank casing interval:	0 ft. to 280 ft.
Blank casing diameter:	5 in.
Casing joints:	Splines
Weight:	_____ lbs/ft.
Wall thickness or gauge no.:	SD17
Blank casing interval:	_____ ft. to _____ ft.
Blank casing diameter:	_____ in.
Casing joints:	
Weight:	_____ lbs/ft.
Wall thickness or gauge no.:	
Grout interval:	Attach ft. to Attach ft.
Grout material:	Attached
Grout interval:	_____ ft. to _____ ft.
Grout material:	

Estimated yield:	15 gpm
Water level was:	_____ ft. after _____ hours pumping _____ gpm
Pump installed?	☐ Yes ✓ No
Water well disinfected?	✓ Yes ☐ No
Date disinfected (mm/dd/yy):	08/17/2022
Aquifer, if known:	

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.:	
KDHE / EPA Project Code:	
Site Name:	
KDHE UIC Class V Form Completed:	☐ Yes ☐ No
County Permit:	☐ Yes ☐ No Permit ID: _____
Lease Name & Well #:	
# of boreholes:	# of dewatering wells:

LITHOLOGIC LOG

FROM	TO	LITHOLOGY INTERVALS
Attach	Attach	Attached

RECEIVED

FEB 09 2026

COMMENTS

Grout 0-5 Other is Gravel Pack for pitless unit

BUREAU OF WATER

CONTRACTOR'S OR LANDOWNERS CERTIFICATION

This water well was constructed ✓ reconstructed ☐ pursuant to the stated water well contractor's license and was completed on 08/17/2022. I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 01/30/2023 under the business name of Nash Water Well Service, LLC, Kansas Water Well Contractor's License No. 846 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Trevor Nash

Send one copy to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.

KANSAS DEPARTMENT OF HEALTH AND ENVIRONMENT

Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka KS 66612-1367
(785) 296-3565 | K.S.A. 82a-1212 | v2022c

Form	WWC5.2 - Water Well Record
Doc ID	1661401
Well Owner	Mitchell Shelton
Contractor	Nash Water Well Service, LLC

Grout

From	To	Grout Material
0	5	Other
5	50	Bentonite
160	180	Bentonite

RECEIVED

FEB 09 2026

BUREAU OF WATER

Form	WWC5.2 - Water Well Record
Doc ID	1661401
Well Owner	Mitchell Shelton
Contractor	Nash Water Well Service, LLC

Lithology

From	To	Lithology Intervals
0	4	topsoil
4	17	clay,*Brown Clay
17	60	sand,fine to coarse
60	75	sand,fine to medium,clayey,tannish,streaks & layers
75	80	sand,fine to coarse,with small to large gravel & tan Brown Clay Streaks
80	90	clay,Tan Brown Clay with Fine medium Sand
90	105	sand,fine to coarse
105	120	sand,fine to coarse,with small to large gravel & small cobble
120	150	sand,fine to medium
150	160	clay,*Whittish Tan Clay
160	170	clay,*White Yellow Clay
170	220	shale,unknown
220	260	other,unknown,*Blue Clay with Gray Sandstone 40%
260	265	other,unknown,*Blue Clay with tight Gray Sandstone 20%
265	300	sandstone,unknown,gray,& Gray Clay 65%
300	380	sandstone,unknown,gray,& Gray Clay 80%

RECEIVED

FEB 09 2026

BUREAU OF WATER

Form	WWC5.2 - Water Well Record
Doc ID	1661401
Well Owner	Mitchell Shelton
Contractor	Nash Water Well Service, LLC

Lithology

From	To	Lithology Intervals
380	400	other,unknown,*Gray Clay with Thin Sandstone Streak 15%

RECEIVED

FEB 09 2026

BUREAU OF WATER