



ASSIGNMENT OF WATER WELL TO LANDOWNER*
FORM WWC-7

I, Larry & Peggy Roe Living Trust of 2426 1300th Rd
(Landowner) (Landowner address)
Oberlin, KS 67749 am the landowner on which a water well is located in the
(City) (State)
1/4, SW 1/4, SE 1/4, NE 1/4, Section 20, Township 17 S, Range 29 E/W, in
Lane _____ County, Kansas, and approximately 2310 feet NS, and 1100 feet EW
of the apparent Reg section corner. The water well was drilled in January 2025 (month/year).

I hereby request that Talon Group LLC leave the water well,
(Well operator/owner name)
which was drilled under Temporary/Term Water Permit # 123024-A, unplugged, and I will assume
all responsibility for properly maintaining said water well in accordance with the requirements of KDHE
regulations in K.A.R. 28-30-6 to 28-30-10, including requesting and maintaining said well in inactive
status and proper plugging when it is abandoned, in accordance with regulations in K.A.R. 28-30-7.

LANDOWNER:

WELL OWNER:

Peggy Roe 4-24-25
(Signature) (Date)
Peggy Roe
(Print)

TALON 04/09/2025
(Signature) (Date)
By: _____
(Agent)

IF ADDITIONAL LANDOWNER

Larry Roe 4-24-25
(Signature) (Date)
Larry Roe
(Print)

RECEIVED

MAY 06 2025

BUREAU OF WATER

*Where the owner of a water well is not the landowner, KDHE regulations in Article 30 [K.A.R. 28-30-7(e)] allow responsibility for the well to be conveyed to the landowner in lieu of abandoning and plugging the well, but the well must conform to the requirements for active or inactive status. The transfer must be made through a legal document, approved by KDHE, advising the landowner of their responsibilities and obligations to properly maintain the well, including the proper plugging of the well when it is abandoned.

Landowners may obtain KDHE's written approval to maintain the well in an inactive status, in accordance with K.A.R. 28-30-7(f), rather than plugging it if the landowner can present evidence as to the well's condition and the landowner's intentions to use the well in the future.

A request for inactive water well status must be submitted to KDHE by completing Form WWC-6 in accordance with Procedure WWP-4. KDHE Water Well Program statutes, regulations, forms, and procedures are available at:

<https://www.kdhe.ks.gov/347/Water-Well-Program>

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1811193 WELL ID _____☒ Original Record ☐ Correction ☐ Change in Well Use**LOCATION OF WATER WELL**

Latitude	<u>38.5634</u>	Longitude	<u>-100.54536</u>	Section	<u>20</u>	Township	<u>17</u>	Range	<u>29</u>	☐ E ☒ W	Fraction	<u>SW ¼ SE ¼ NE ¼</u>
Datum	<u>WGS84</u>	Elevation	<u>2821</u>	County	<u>Lane</u>							

WATER WELL OWNER

Name	
Business	<u>Talon Group LLC</u>
Address	<u>PO Box 700</u> <u>Hays KS 67601</u>
Well location	<u>W RD 200 and N. Gage RD</u>
☐ at owner's address	

WELL WATER USE

Industrial OilFieldWaterSupply

COMPLETIONDepth of completed well: 150 ft.

Depth(s) groundwater encountered:

(1) _____ ft.; (2) _____ ft.;

(3) _____ ft.; (4) ☐ dry wellStatic water level in well: 100 ft.☒ measured below land surface
on (mm/dd/yy): 01/02/2025☐ measured above land surface
on (mm/dd/yy): _____Estimated yield: 50 gpmWater level was: _____ ft. after _____ hours
pumping _____ gpmPump installed? ☐ Yes ☒ NoWater well disinfected? ☒ Yes ☐ NoDate disinfected (mm/dd/yy): 01/02/2025

Aquifer, if known: _____

NEAREST SOURCE OF POTENTIAL CONTAMINATION

Source: _____
Distance from well: _____ Direction from well: _____
Source description: _____
Source: _____
Distance from well: _____ Direction from well: _____
Source description: _____
☒ No potential source of contamination within 100 feet.

CONSTRUCTION

Borehole interval: from <u>0</u> to <u>150</u> ft.	Borehole diameter: <u>8</u> in.
from _____ to _____ ft.	_____ in.
Casing height above land surface: <u>18</u> in.	
If casing height is less than 12 in. has a variance been approved? ☐ Yes ☒ No	
*variance not required for monitoring or environmental remediation wells	
Casing type: <u>ThermalPlastic</u>	
Blank casing interval: <u>0</u> ft. to <u>110</u> ft.	
Blank casing diameter: <u>4.5</u> in.	
Casing joints: <u>Glued</u>	
Weight: <u>2.38</u> lbs/ft.	
Wall thickness or gauge no.: <u>.237</u>	
Blank casing interval: _____ ft. to _____ ft.	
Blank casing diameter: _____ in.	
Casing joints: _____	
Weight: _____ lbs/ft.	
Wall thickness or gauge no.: _____	
Grout interval: <u>0</u> ft. to <u>25</u> ft.	
Grout material: <u>Bentonite</u>	
Grout interval: _____ ft. to _____ ft.	
Grout material: _____	
Screen / perforation material: <u>PVC</u>	
Screen / perforation openings: <u>Saw cut</u>	
Screen / perforation intervals: From <u>110</u> ft. to <u>150</u> ft.	
Slot size _____ unit	
From _____ ft. to _____ ft.	
Slot size _____ unit	
Gravel pack intervals:	
Gravel pack not used: ☐ Gravel size _____ in	
From <u>25</u> ft. to <u>150</u> ft.	
Gravel pack not used: ☐ Gravel size _____ in	
From _____ ft. to _____ ft.	

LITHOLOGIC LOG

FROM	TO	LITHOLOGY INTERVALS
Attached	Attached	Attached

COMMENTS

--

CONTRACTOR'S OR LANDOWNERS CERTIFICATION

This water well was constructed ☒ reconstructed ☐ pursuant to the stated water well contractor's license and was completed on <u>01/02/2025</u> . I certify that this record is true to the best of my knowledge and belief. This water well record was completed on <u>02/27/2025</u> under the business name of <u>Woofert Pump & Well, Inc. #881</u> , Kansas Water Well Contractor's License No. <u>881</u> under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: <u>Lance Shepard</u> .
--

Send one copy to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.

Form	WWC5.2 - Water Well Record
Doc ID	1811193
Well Owner	Talon Group LLC
Contractor	Woofter Pump & Well, Inc. #881

Lithology

From	To	Lithology Intervals
0	2	topsoil
2	10	loess,medium
10	29	other,Clay w/ tr caliche
29	43	other,Clay & caliche w/ tr fine sand
43	64	other,Clay & caliche w/ fine sand streaks
64	101	other,Fine to some med sand w/ clay & caliche lenses
101	130	other,Fine sand with clay lenses
130	134	other,Fine & Med sand w/ small gravel
134	150	other,Yellow Ochre/Black Shale