

County: Dickinson -KGS/DRL

WATER WELL RECORD Form WWC-5

☒ Original Record ☐ Correction ☐ Change in Well Use

Division of Water
Resources App. No.

Well ID

1 LOCATION OF WATER WELL: County: <u>GEARY</u>		Fraction <u>SE 1/4 SW 1/4 SE 1/4</u>	Section Number <u>9</u>	Township Number <u>T 13 S</u>	Range Number <u>R 4 E W</u>
2 WELL OWNER: Last Name: <u>BRINKMAN</u> First: <u>AARON</u> Business: <u>P.O. BOX 1204</u> Address: <u>JUNCTION CITY</u> City: <u>KS</u> State: <u>KS</u> ZIP: <u>66441</u>		Street or Rural Address where well is located (if unknown, distance and direction from nearest town or intersection): If at owner's address, check here: ☐ <u>FROM 2300+ TRAIL GO 1/2 MILE WEST 100 yards North in pasture</u>			
3 LOCATE WELL WITH "X" IN SECTION BOX: N W E S 1 mile	4 DEPTH OF COMPLETED WELL: <u>140</u> ft. Depth(s) Groundwater Encountered: 1) <u>112</u> ft. 2) ft. 3) ft. or 4) ☐ Dry Well WELL'S STATIC WATER LEVEL: <u>1001</u> ft. ☒ below land surface, measured on (mo-day-yr) <u>5/13/2026</u> ☐ above land surface, measured on (mo-day-yr) Pump test data: Well water was ft. after hours pumping gpm Well water was ft. after hours pumping gpm Estimated Yield: <u>9</u> gpm Bore Hole Diameter: <u>9"</u> in. to <u>140</u> ft. and in. to ft.		5 Latitude: <u>N 38° 55.810</u> (decimal degrees) Longitude: <u>W 096° 59.259</u> (decimal degrees) Horizontal Datum: ☒ WGS 84 ☐ NAD 83 ☐ NAD 27 Source for Latitude/Longitude: ☐ GPS (unit make/model: <u>Garmin E-Trex 30</u>) (WAAS enabled? ☐ Yes ☐ No) ☐ Land Survey ☐ Topographic Map ☐ Online Mapper:		
		6 Elevation: <u>1225'</u> ft. ☒ Ground Level ☐ TOC Source: ☐ Land Survey ☒ GPS ☐ Topographic Map ☐ Other			

7 WELL WATER TO BE USED AS:

1. ☒ Domestic: ☒ Household ☐ Lawn & Garden ☐ Livestock	2. ☐ Irrigation	3. ☐ Feedlot	4. ☐ Industrial	5. ☐ Public Water Supply: well ID	6. ☐ Dewatering: how many wells?	7. ☐ Aquifer Recharge: well ID	8. ☐ Monitoring: well ID	9. Environmental Remediation: well ID	10. ☐ Oil Field Water Supply: lease	11. Test Hole: well ID	12. Geothermal: how many bores?	13. ☐ Other (specify):
---	--	-------------------------------------	--	--	---	---	---	---	--	------------------------------	---------------------------------------	---

Was a chemical/bacteriological sample submitted to KDHE? ☐ Yes ☒ No If yes, date sample was submitted:

Water well disinfected? ☒ Yes ☐ No

8 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded

Casing diameter 5" in. to 120' ft. Diameter in. to ft. Diameter in. to ft. Diameter in. to ft.

Casing height above land surface 3' in. Weight 506.40 lbs./ft. Wall thickness or gauge No.

TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC ☐ Other (Specify) MAY 26 2026

☐ Brass ☐ Galvanized Steel ☐ Concrete tile ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:
☐ Continuous Slot ☒ Mill Slot ☐ Gauze Wrapped ☐ Torch Cut ☐ Drilled Holes ☐ Other (Specify)

☐ Louvered Shutter ☐ Key Punched ☐ Wire Wrapped ☐ Saw Cut ☐ None (Open Hole)

SCREEN-PERFORATED INTERVALS: From 120 ft. to 140 ft. From ft. to ft. From ft. to ft. From ft. to ft.

GRAVEL PACK INTERVALS: From 30 ft. to 140 ft. From ft. to ft. From ft. to ft. From ft. to ft.

9 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other

Grout Intervals: From 5 ft. to 30 ft. From ft. to ft. From ft. to ft. From ft. to ft.

Nearest source of possible contamination: None Close

☐ Septic Tank	☐ Lateral Lines	☐ Pit Privy	☐ Livestock Pens	☐ Insecticide Storage
☐ Sewer Lines	☐ Cess Pool	☐ Sewage Lagoon	☐ Fuel Storage	☐ Abandoned Water Well
☐ Watertight Sewer Lines	☐ Seepage Pit	☐ Feedyard	☐ Fertilizer Storage	☐ Oil Well/Gas Well
☐ Other (Specify)				

Direction from well? Distance from well? ft.

10 FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	1	Top Soil	88	94	Limstone
1	6	Brown Clay	94	112	Brown Shale
6	14	limstone	112	122	limstone
14	19	Brown Shale	122	131	Grey Shale
19	23	limstone	131	140	limstone
23	42	Tan Shale			
42	78	Brown Shale			
78	81	limstone			
81	88	Brown Shale			

Notes:

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo-day-year) 5/13/2026 and this record is true to the best of my knowledge and belief.

Kansas Water Well Contractor's License No. 481 This Water Well Record was completed on (mo-day-year) 5/18/2026

under the business name of Haroldman Well Drilling Geary Co. KS

Mail 1 white copy along with a fee of \$5.00 for each constructed well to: Kansas Department of Health and Environment, Bureau of Water, GWTS Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Mail one to Water Well Owner and retain one for your records. Telephone 785-296-5524.

Visit us at <http://www.kdheks.gov/waterwell/index.html> KSA 82a-1212 Revised 1/20/2015