

Correction

KOLAR Document ID: 1894156

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1894156

WELL ID

LOCATION OF WATER WELL

County	Gray	Section	33	Township	25	Range	28 ☐ E ☒ W	Fraction	SE ¼ SE ¼ SW ¼
Latitude	37.827875	Longitude	-100.403447	Datum	WGS84	Elevation	2756		

WATER WELL LOCATION

☐ at owner's address

From the intersection of 15 Road and M Road, 2,000 feet East and 100 foot North

WATER WELL OWNER

Name	
Business	Cimarron Crossing Feeders
Address	PO Box 349
	Cimarron KS 67835

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: 51,373
KDHE / EPA Project Code: _____
Site Name: _____
KDHE UIC Class V Form Completed: ☐ Yes ☐ No
County/Local Permit Required? ☐ Yes ☐ No
Permit Obtained? ☐ Yes ☒ No Permit ID: _____
Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 18 in.
Is casing height less than 12 inches? ☐ Yes ☒ No
Blank Casing type: ThermalPlastic
1st interval: 0 ft. to 400 ft.; Diameter 10 in.
Casing Joint: Splines Weight: _____ lbs/ft
Wall thickness or gauge no.: SDR17
2nd interval: _____ ft. to _____ ft.; Diameter _____ in.
Casing Joint: _____ Weight: _____ lbs/ft
Wall thickness or gauge no.: _____
3rd interval: _____ ft. to _____ ft.; Diameter _____ in.
Casing Joint: _____ Weight: _____ lbs/ft
Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Saw cut

1st interval 400 ft. to 740 ft. Slot Size .32 millim
2nd interval _____ ft. to _____ ft. Slot Size _____
3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Irrigation

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETION

Depth of completed well: 740 ft.

Depth(s) groundwater encountered: ☐ Dry Well

(1) 160 ft.; (2) 400 ft.; (3) _____ ft.;

Static water level in well: 382 ft.

Date measured: 02/20/2026

Measured from: ☒ Top of Casing or ☐ Ground SurfaceMeasured: ☐ Above or ☒ Below Land Surface

Estimated yield: 950 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:

Pump Installed? ☐ Yes ☒ No Date:

Pump Type: Horsepower: Volts:

Drop Pipe Diameter: in. Drop Pipe Length: ft.

Water well disinfected? ☒ Yes ☐ No

Date disinfected (mm/dd/yy): 02/20/2026

CONSTRUCTION

Borehole interval:

from 0 to 740 ft.

from _____ to _____ ft.

from _____ to _____ ft.

Borehole diameter:

17.7 in.

_____ in.

_____ in.

Grout:

1st Interval: 0 ft. to 40 ft. Grout material: Bentonite

2nd Interval: 270 ft. to 300 ft. Grout material: Bentonite

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

1st Interval: 40 ft. to 270 ft. Gravel Size: _____ ☐ Not Used2nd Interval: 300 ft. to 740 ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐

DESIGNATED PERSON Trevor Nash

WELL COMPLETION DATE 02/20/2026

CONTRACTOR BUSINESS NAME

Nash Water Well Service, LLC

JUN 08 2026

KOLAR DOC ID 1894156 WELL ID

County	Gray	Section	33	Township	25	Range	28	☒ E ☒ W	Fraction	SE ¼	SE ¼	SW ¼
Latitude	37.827875	Longitude	-100.403447		Datum		WGS84		Elevation	2756		
Well Owner				Well Owner Business			Cimarron Crossing Feeders					

NEAREST SOURCE OF POTENTIAL CONTAMINATION		or	☐ No potential source of contamination within 100 ft.
Source: Other (please specify)		Source:	
Distance from well (ft): 100	Direction from well: E	Distance from well (ft):	Direction from well:
Source description: Feedyard Lagoon		Source description:	
Required information for local entity? ☐ Yes ☐ No		Required information for local entity? ☐ Yes ☐ No	

[illegible]

Appropriation of Water File No.51,373
Water Right File Nos. 11,511-D1 , 11,511-D2 and
40,238

RECEIVED

JUN 08 2026

This water well was constructed/reconstructed pursuant to the stated water well contractor's license and was completed on 02/20/2026. I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 03/20/2026 under the business name of Nash Water Well Service, LLC, KS Water Well Contractor's License No. 846 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Trevor Nash. Send one copy to the water well owner and the contractor should retain one copy.

Form	WWC5.2 - Water Well Record
Doc ID	1894156
Well Owner	Cimarron Crossing Feeders
Contractor	Nash Water Well Service, LLC

Lithology

From	To	Lithology Intervals
0	3	topsoil
3	10	clay,sandy,tan,fine
10	20	clay,sandy,tan,red clay, fine
20	35	clay,sandy,tan,fine
35	40	clay,sandy,tan,red, fine
40	60	clay,sandy,tan,w/ white rock, fine sand
60	100	sand,fine to coarse,gravelly,w/ streaks of small to large gravel
100	120	sand,fine to coarse,clayey,tannish,streaks
120	160	sand,fine to coarse,gravelly,small streaks, tan clay
160	180	sand,fine to medium
180	271	sand,fine to medium,clayey,tannish
271	400	shale,unknown,blue,w/ rock streaks & layers
400	420	shale,unknown,blue,w/ gray fine sandstone Medium 20%
420	440	other,unknown,black,clay w/ fine gray sandstone Medium 15%
440	460	other,unknown,blue,clay
460	480	sandstone,unknown,gray,Fine , gray clay Medium 85%

RECEIVED

JUN 08 2026

BUREAU OF WATER

Form	WWC5.2 - Water Well Record
Doc ID	1894156
Well Owner	Cimarron Crossing Feeders
Contractor	Nash Water Well Service, LLC

Lithology

From	To	Lithology Intervals
480	500	sandstone,unknown,gray,Fine , gray clay Medium 30%
500	520	sandstone,unknown,gray,Fine , gray clay Medium 70%
520	540	sandstone,unknown,gray,Fine , gray clay Medium 80%
540	560	sandstone,unknown,Medium coarse, Gray Blue Clay Medium 85%
560	580	sandstone,unknown,Medium coarse, Gray Blue Clay Medium 9%
580	600	other,unknown,gray,blue clay, medium gray sandstone Medium 35%
600	620	sandstone,unknown,tan,Medium coarse, gray blue clay Medium 85%
620	640	sandstone,unknown,tan,Medium coarse, gray blue clay Medium 90%
640	660	sandstone,unknown,tan,Medium coarse, thin gray clay streaks Loose 95%
660	680	sandstone,unknown,tan,Medium coarse, thin gray clay streaks Loose 95%
680	700	sandstone,unknown,tan,Medium coarse,thin gray clay streaks Loose 95%

RECEIVED

JUN 08 2026

BUREAU OF WATER

Form	WWC5.2 - Water Well Record
Doc ID	1894156
Well Owner	Cimarron Crossing Feeders
Contractor	Nash Water Well Service, LLC

Lithology

From	To	Lithology Intervals
700	720	sandstone,unknown,tan,Medium coarse, thin gray clay streaks Loose 95%
720	740	sandstone,unknown,gray,Medium fine, blue gray clay streaks Medium 80%
740	760	other,unknown,blue,gray clay, thin streaks of fine gray sandstone Medium 10%

RECEIVED

JUN 08 2026

BUREAU OF WATER