

Corrected

WATER WELL RECORD (WWC5.2)

Constructed

KOLAR DOC ID 1872989

WELL ID _____

LOCATION OF WATER WELL

County	Seward	Section	12	Township	33	Range	31 ☐ E ☒ W	Fraction	NW ¼ SW ¼ SW ¼
Latitude	37.187237	Longitude	-100.653	Datum	WGS84	Elevation	2761		

WATER WELL LOCATION

☒ at owner's address

WATER WELL OWNER

Name	
Business	High Plains Ponderosa Dairy
Address	2042 V Road Plains KS 67869

PERMIT & ID NUMBERS (AS REQUIRED)

DWR Application No.: _____

KDHE / EPA Project Code: _____

Site Name: _____

KDHE UIC Class V Form Completed: ☐ Yes ☐ No

County/Local Permit Required? ☐ Yes ☐ No

Permit Obtained? ☒ Yes ☐ No Permit ID: 1229

Oil/Gas Lease Name & Well #: _____

CONSTRUCTION

Casing: Height above land surface: 24 in.

Is casing height less than 12 inches? ☐ Yes ☒ No

Blank Casing type: ThermalPlastic

1st interval: 0 ft. to 400 ft.; Diameter 8 in.

Casing Joint: Splines Weight: _____ lbs/ft

Wall thickness or gauge no.: SDR 17

2nd interval: _____ ft. to _____ ft.; Diameter _____ in.

Casing Joint: _____ Weight: _____ lbs/ft

Wall thickness or gauge no.: _____

3rd interval: _____ ft. to _____ ft.; Diameter _____ in.

Casing Joint: _____ Weight: _____ lbs/ft

Wall thickness or gauge no.: _____

Screen / Perforation material: PVC

Specify if other: _____

Screen / Perforation openings: Saw cut

1st interval 400 ft. to 500 ft. Slot Size .32 millim

2nd interval _____ ft. to _____ ft. Slot Size _____

3rd interval _____ ft. to _____ ft. Slot Size _____

WELL WATER USE

Domestic Household

Additional info if required:

of Boreholes

of Dewatering Wells

COMPLETION

Depth of completed well: 500 ft.Depth(s) groundwater encountered: ☐ Dry Well(1) 298 ft.; (2) _____ ft.; (3) _____ ft.;Static water level in well: 298 ft.Date measured: 01/09/2026Measured from: ☒ Top of Casing or ☐ Ground SurfaceMeasured: ☐ Above or ☒ Below Land SurfaceEstimated yield: 100 gpm

Pump Test Date: Water level was:

_____ ft. after _____ hours pumping _____ gpm

_____ ft. after _____ hours pumping _____ gpm

Pump Information:

Pump Installed? ☐ Yes ☒ No Date: _____

Pump Type: _____ Horsepower: _____ Volts: _____

Drop Pipe Diameter: _____ in. Drop Pipe Length: _____ ft.

Water well disinfected? ☒ Yes ☐ NoDate disinfected (mm/dd/yy): 01/09/2026

CONSTRUCTION

Borehole interval:

from 0 to 500 ft.

from _____ to _____ ft.

from _____ to _____ ft..

Borehole diameter:

12.7 in.

_____ in.

_____ in.

Grout:

1st Interval: 5 ft. to 40 ft. Grout material: Bentonite2nd Interval: 240 ft. to 260 ft. Grout material: Bentonite

3rd Interval: _____ ft. to _____ ft. Grout material: _____

Gravel pack:

Not Used

1st Interval: 40 ft. to 240 ft. Gravel Size: _____ ☐2nd Interval: 260 ft. to 500 ft. Gravel Size: _____ ☐3rd Interval: _____ ft. to _____ ft. Gravel Size: _____ ☐

DESIGNATED PERSON: Trevor Nash

WELL COMPLETION DATE 01/09/2026

CONTRACTOR BUSINESS NAME

Nash Water Well Service, LLC

WATER WELL RECORD (WWC-5)

Constructed

KOLAR DOC ID 1872989 WELL ID _____

LOCATION OF WATER WELL

County	Seward	Section	12	Township	33	Range	31 ^E / _W	Fraction	NW $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$
Latitude	37.187237	Longitude	-100.653	Datum	WGS84	Elevation	2761		
Well Owner		Well Owner Business	High Plains Ponderosa Dairy						

NEAREST SOURCE OF POTENTIAL CONTAMINATION or ☒ No potential source of contamination within 100 ft.

Source:	Source:
Distance from well (ft):	Distance from well (ft):
Direction from well:	Direction from well:
Source description:	Source description:
Required information for local entity? ☐ Yes ☐ No	Required information for local entity? ☐ Yes ☐ No

LITHOLOGIC LOG**AQUIFER, if known**

FROM	TO	LITHOLOGY
0	5	topsoil
5	20	sand, fine
20	60	clay, sandy, tan, fine streaks
60	80	clay, sandy, brown, Tan Red, fine course streaks
80	95	clay, tan
95	115	sand, fine to coarse, gravelly, small to large
115	120	clay, brown
120	170	sand, fine to coarse, w/small to large gravel
170	180	clay, Brown/tan/gray clay w/ fine course sand
180	255	sand, fine to coarse
255	310	clay, Gray/blue clay
310	320	sand, fine to medium
320	400	sand, fine to coarse
400	460	sand, fine to coarse
460	500	clay, Tan/gray/blue clay w/fine medium sand

COMMENTS	This water well was constructed reconstructed pursuant to the stated water well contractor's license and was completed on 01/09/2026 . I certify that this record is true to the best of my knowledge and belief. This water well record was completed on 03/20/2026 under the business name of Nash Water Well Service, LLC , KS Water Well Contractor's License No. 846 under the authority of the designated person as defined in K.A.R. 28-30-2(j) and signed and certified by the electronic signature of the designated person at its submittal: Trevor Nash . Send one copy to the water well owner and the contractor should retain one copy.
-----------------	---

RECEIVED**JUN 08 2026**

Page 2

KANSAS DEPARTMENT OF HEALTH AND ENVIRONMENT
Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka KS 66612-1367

K.S.A. 82a-1212
v2024c

BUREAU OF WATER