

WATER WELL RECORD Form WWC-5

☒ Original Record ☐ Correction ☐ Change in Well Use

Division of Water
Resources App. No.

Well ID

1 LOCATION OF WATER WELL:

County: Dickinson

Fraction

NW, SW, NE 1/4

Section Number

35

Township Number

T 12 S

Range Number

R 3 E ☐ W

2 WELL OWNER: Last Name:

JURY

First: Tim

Street or Rural Address where well is located (if unknown, distance and direction from nearest town or intersection): If at owner's address, check here: ☐
From Point 2600 Ave Go West 4 1/2 miles
+ 1/2 mile south in pasture

Business:

Address:

City:

910 Nicholson Rd.


Chapman

State: KS

ZIP: 67431

3 LOCATE WELL WITH "X" IN SECTION BOX:

N



S

4 DEPTH OF COMPLETED WELL:

Depth(s) Groundwater Encountered: 1) 108 ft.

2) 108 ft. 3) 108 ft. or 4) ☐ Dry Well

WELL'S STATIC WATER LEVEL: 90 ft. 8/5/2025

☒ below land surface, measured on (mo-day-yr)

☐ above land surface, measured on (mo-day-yr)

Pump test data: Well water was 160 ft.

after 20 hours pumping 20 gpm

Well water was 160 ft.

after 20 hours pumping 20 gpm

Estimated Yield: 20 gpm

Bore Hole Diameter: 31 in. to 160 ft. and

160 in. to 160 ft.

5 Latitude: N 38° 58.161 (decimal degrees)

Longitude: W 097° 03.844 (decimal degrees)

Horizontal Datum: ☒ WGS 84 ☐ NAD 83 ☐ NAD 27

Source for Latitude/Longitude:

☒ GPS (unit make/model: Garmin E T61x 20)

(WAAS enabled? ☐ Yes ☐ No)

☐ Land Survey ☐ Topographic Map

☐ Online Mapper: Google Earth

6 Elevation: 1,226 ft. ☒ Ground Level ☐ TOC

Source: ☐ Land Survey ☒ GPS ☐ Topographic Map

☐ Other: None

7 WELL WATER TO BE USED AS:

1. Domestic:

- ☐ Household
☐ Lawn & Garden
☒ Livestock

2. ☐ Irrigation

3. ☐ Feedlot

4. ☐ Industrial

5. ☐ Public Water Supply: well ID

6. ☐ Dewatering: how many wells?

7. ☐ Aquifer Recharge: well ID

8. ☐ Monitoring: well ID

9. Environmental Remediation: well ID

☐ Air Sparge ☐ Soil Vapor Extraction

☐ Recovery ☐ Injection

10. ☐ Oil Field Water Supply: lease

11. Test Hole: well ID

☐ Cased ☐ Uncased ☐ Geotechnical

12. Geothermal: how many bores?

a) Closed Loop ☐ Horizontal ☐ Vertical

b) Open Loop ☐ Surface Discharge ☐ Inj. of Water

13. ☐ Other (specify):

Was a chemical/bacteriological sample submitted to KDHE? ☐ Yes ☒ No

Water well disinfected? ☒ Yes ☐ No

If yes, date sample was submitted:

8 TYPE OF CASING USED:

☐ Steel ☒ PVC ☐ Other

CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded

Casing diameter 5 in. to 140 ft. Diameter 5 in. to 140 ft. Diameter 5 in. to 140 ft.

Casing height above land surface 31 in. Weight 5440 lbs./ft. Wall thickness or gauge No.

TYPE OF SCREEN OR PERFORATION MATERIAL:

- ☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC
☐ Brass ☐ Galvanized Steel ☐ Concrete tile ☐ None used (open hole)

☐ Other (Specify):

SCREEN OR PERFORATION OPENINGS ARE:

- ☐ Continuous Slot ☒ Mill Slot ☐ Gauze Wrapped ☐ Torch Cut ☐ Drilled Holes ☐ Other (Specify)
☐ Louvered Shutter ☐ Key Punched ☐ Wire Wrapped ☐ Saw Cut ☐ None (Open Hole)

SCREEN-PERFORATED INTERVALS: From 140 ft. to 160 ft. From 140 ft. to 160 ft. From 140 ft. to 160 ft.

GRAVEL PACK INTERVALS: From 31 ft. to 160 ft. From 31 ft. to 160 ft. From 31 ft. to 160 ft.

9 GROUT MATERIAL:

☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other

Grout Intervals: From 4 ft. to 31 ft. From 4 ft. to 31 ft. From 4 ft. to 31 ft.

Nearest source of possible contamination:

None Close

- ☐ Septic Tank ☐ Lateral Lines ☐ Pit Privy ☐ Livestock Pens ☐ Insecticide Storage
☐ Sewer Lines ☐ Cess Pool ☐ Sewage Lagoon ☐ Fuel Storage ☐ Abandoned Water Well
☐ Watertight Sewer Lines ☐ Seepage Pit ☐ Feedyard ☐ Fertilizer Storage ☐ Oil Well/Gas Well
☐ Other (Specify):

Direction from well? Distance from well? ft.

10 FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
<u>0</u>	<u>1</u>	<u>Top Soil</u>	<u>108</u>	<u>115</u>	<u>Limestone</u>
<u>1</u>	<u>4</u>	<u>Brown Clay</u>	<u>115</u>	<u>126</u>	<u>Tan Shale</u>
<u>4</u>	<u>15</u>	<u>Sandy Clay</u>	<u>126</u>	<u>155</u>	<u>Limestone</u>
<u>15</u>	<u>18</u>	<u>Brown Clay</u>	<u>155</u>	<u>160</u>	<u>Gray Shale</u>
<u>18</u>	<u>31</u>	<u>Greenish Shale</u>			
<u>31</u>	<u>38</u>	<u>Limestone</u>			
<u>38</u>	<u>71</u>	<u>Brown Shale</u>			
<u>71</u>	<u>87</u>	<u>Limestone</u>			
<u>87</u>	<u>108</u>	<u>Brown Shale</u>			

Notes:

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo-day-year) 8/5/2025 and this record is true to the best of my knowledge and belief.

Kansas Water Well Contractor's License No. 451 This Water Well Record was completed on (mo-day-year) 8/6/2025

under the business name of Waldman Well Drilling

Mail 1 white copy along with a fee of \$5.00 for each constructed well to: Kansas Department of Health and Environment, Bureau of Water, GWTS Section,

1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Mail one to Water Well Owner and retain one for your records. Telephone 785-296-5524.

Visit us at <http://www.kdheks.gov/waterwell/index.html>

KSA 82a-1212

Revised 1/20/2015