

WATER WELL RECORD Form WWC-5

☒ Original Record ☐ Correction ☐ Change in Well Use


Division of Water
Resources App. No.

Well ID

MW-38B1

1 LOCATION OF WATER WELL: County: Johnson		Fraction SE ¼ SE ¼ NW ¼ ¼	Section Number 36	Township Number T 13 S	Range Number R 23 ☒ E ☐ W
---	--	------------------------------	----------------------	---------------------------	---

2 WELL OWNER: Last Name: First: Business: The Boeing Company Address: 2727 E MacArthur Address: City: Wichita State: KS ZIP: 67216		Street or Rural Address where well is located (if unknown, distance and direction from nearest town or intersection): If at owner's address, check here: ☐ On Ocheltree St. Approximately 250 ft South from the intersection of S. Ocheltree St. and E. Glendale St.
---	--	--

3 LOCATE WELL WITH "X" IN SECTION BOX: N  W E S -----1 mile-----	4 DEPTH OF COMPLETED WELL:24..... ft. Depth(s) Groundwater Encountered: 1) ft. 2) ft. 3) ft., or 4) ☐ Dry Well WELL'S STATIC WATER LEVEL:14.00..... ft. ☒ below land surface, measured on (mo-day-yr) 11/22/2025 ☐ above land surface, measured on (mo-day-yr) Pump test data: Well water was ft. after hours pumping gpm Well water was ft. after hours pumping gpm Estimated Yield: gpm Bore Hole Diameter: 12.25 in. to 17.5 ft. and 8.2 in. to 24 ft.	5 Latitude:38.87758889.....(decimal degrees) Longitude:-94.80708333333333.....(decimal degrees) Horizontal Datum: ☐ WGS 84 ☒ NAD 83 ☐ NAD 27 Source for Latitude/Longitude: ☐ GPS (unit make/model:) (WAAS enabled? ☐ Yes ☐ No) ☒ Land Survey ☐ Topographic Map ☐ Online Mapper:
	6 Elevation: 1050.13ft. ☒ Ground Level ☐ TOC Source: ☒ Land Survey ☐ GPS ☐ Topographic Map ☐ Other	

7 WELL WATER TO BE USED AS:

1. Domestic: ☐ Household ☐ Lawn & Garden ☐ Livestock	2. ☐ Irrigation	3. ☐ Feedlot	4. ☐ Industrial	5. ☐ Public Water Supply: well ID	6. ☐ Dewatering: how many wells?	7. ☐ Aquifer Recharge: well ID	8. ☒ Monitoring: well ID MW-38B1	9. Environmental Remediation: well ID	10. ☐ Oil Field Water Supply: lease	11. Test Hole: well ID	12. Geothermal: how many bores?	13. ☐ Other (specify):
				☐ Air Sparge ☐ Soil Vapor Extraction								
				☐ Recovery ☐ Injection								

Was a chemical/bacteriological sample submitted to KDHE? ☐ Yes ☒ No If yes, date sample was submitted:
 Water well disinfected? ☐ Yes ☒ No

8 TYPE OF CASING USED: ☒ Steel ☐ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☒ Welded ☐ Threaded
 Casing diameter4..... in. to19..... ft., Diameter9.4..... in. to17.5..... ft., Diameter in. to ft.
 Casing height above land surface-4..... in. Weight lbs./ft. Wall thickness or gauge No. Sch. 40.....
TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC ☐ Other (Specify)
☐ Brass ☐ Galvanized Steel ☐ Concrete tile ☐ None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:
☐ Continuous Slot ☒ Mill Slot ☐ Gauze Wrapped ☐ Torch Cut ☐ Drilled Holes ☐ Other (Specify)
☐ Louvered Shutter ☐ Key Punched ☐ Wire Wrapped ☐ Saw Cut ☐ None (Open Hole)
SCREEN-PERFORATED INTERVALS: From19..... ft. to24..... ft., From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS: From18..... ft. to24..... ft., From ft. to ft., From ft. to ft.

9 GROUT MATERIAL: ☐ Neat cement ☒ Cement grout ☐ Bentonite ☐ Other
 Grout Intervals: From0..... ft. to15..... ft., From15..... ft. to18..... ft., From ft. to ft.
Nearest source of possible contamination:
☐ Septic Tank ☐ Lateral Lines ☐ Pit Privy ☐ Livestock Pens ☐ Insecticide Storage
☐ Sewer Lines ☐ Cess Pool ☐ Sewage Lagoon ☐ Fuel Storage ☐ Abandoned Water Well
☐ Watertight Sewer Lines ☐ Seepage Pit ☐ Feedyard ☐ Fertilizer Storage ☐ Oil Well/Gas Well
☒ Other (Specify) Former Chemical Commodities, Inc. Site
 Direction from well? NE Distance from well? ~620 ft.

10 FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	5.5	Hydrovac for Utility Clearance			
5.5	15.25	Silty Clay			
15.25	17.5	Moderately weathered limestone			
17.5	20	Limestone			
20	22.8	Moderately weathered sandstone			
22.8	24	Shale			

Notes:

RECEIVED

DEC 29 2025

BUREAU OF WATER

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo-day-year) 11/22/2025 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 1031. This Water Well Record was completed on (mo-day-year) 12/19/2025 under the business name of Environmental Works, Inc. Signature Daniel Yoakum

Mail 1 white copy along with a fee of \$5.00 for each constructed well to: Kansas Department of Health and Environment, Bureau of Water, GWTS Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Mail one to Water Well Owner and retain one for your records. Telephone 785-296-5524.

Visit us at <http://www.kdheks.gov/waterwell/index.html>

KSA 82a-1212

Revised 7/10/2015

GIS FILE PATH: \\haleyaldrich.com\share\CFIP\Projects\0129498\GIS\MapProjects\2025_07\129498_060_CCI_FIGURES.aprx - USER: dfm - LAST SAVED: 1/23/2026 11:13 AM

