

WATER WELL RECORD Form WWC-5

☒ Original Record ☐ Correction ☐ Change in Well Use


Division of Water
Resources App. No.

Well ID

MW-55C

1 LOCATION OF WATER WELL: County: Johnson		Fraction SE ¼ SE ¼ NW ¼ ¼	Section Number 36	Township Number T 13 S	Range Number R 23 ☒ E ☐ W
---	--	------------------------------	----------------------	---------------------------	---

2 WELL OWNER: Last Name: First: Business: The Boeing Company Address: 2727 E MacArthur Address: City: Wichita State: KS ZIP: 67216		Street or Rural Address where well is located (if unknown, distance and direction from nearest town or intersection): If at owner's address, check here: ☐ On S. Keeler St. Approximately 150 ft South from the intersection of S. Keeler St. and E. Cedar St.
---	--	--

3 LOCATE WELL WITH "X" IN SECTION BOX: N  S -----1 mile-----	4 DEPTH OF COMPLETED WELL:27..... ft. Depth(s) Groundwater Encountered: 1) ft. 2) ft. 3) ft., or 4) ☐ Dry Well WELL'S STATIC WATER LEVEL:21.82..... ft. ☒ below land surface, measured on (mo-day-yr) 11/22/2025 ☐ above land surface, measured on (mo-day-yr) Pump test data: Well water was ft. after hours pumping gpm Well water was ft. after hours pumping gpm Estimated Yield: gpm Bore Hole Diameter: 10.75 in. to 24 ft. and 6.1 in. to 27 ft.	5 Latitude:38.87872778.....(decimal degrees) Longitude:-94.80600278.....(decimal degrees) Horizontal Datum: ☐ WGS 84 ☒ NAD 83 ☐ NAD 27 Source for Latitude/Longitude: ☐ GPS (unit make/model:) (WAAS enabled? ☐ Yes ☐ No) ☒ Land Survey ☐ Topographic Map ☐ Online Mapper:
	6 Elevation: 1051.88ft. ☒ Ground Level ☐ TOC Source: ☒ Land Survey ☐ GPS ☐ Topographic Map ☐ Other	

7 WELL WATER TO BE USED AS: 1. Domestic: ☐ Household ☐ Lawn & Garden ☐ Livestock 2. ☐ Irrigation 3. ☐ Feedlot 4. ☐ Industrial 5. ☐ Public Water Supply: well ID 6. ☐ Dewatering: how many wells? 7. ☐ Aquifer Recharge: well ID 8. ☒ Monitoring: well ID MW-55C 9. Environmental Remediation: well ID ☐ Air Sparge ☐ Soil Vapor Extraction ☐ Recovery ☐ Injection 10. ☐ Oil Field Water Supply: lease 11. Test Hole: well ID ☐ Cased ☐ Uncased ☐ Geotechnical 12. Geothermal: how many bores? a) Closed Loop ☐ Horizontal ☐ Vertical b) Open Loop ☐ Surface Discharge ☐ Inj. of Water 13. ☐ Other (specify):		
--	--	--

Was a chemical/bacteriological sample submitted to KDHE? ☐ Yes ☒ No If yes, date sample was submitted:
 Water well disinfected? ☐ Yes ☒ No

8 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☒ Threaded
 Casing diameter2..... in. to 24 ft., Diameter6.625..... in. to 24 ft., Diameter in. to ft.
 Casing height above land surface4..... in. Weight lbs./ft. Wall thickness or gauge No. Sch. 40

TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC ☐ Other (Specify)
☐ Brass ☐ Galvanized Steel ☐ Concrete tile ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:
☐ Continuous Slot ☒ Mill Slot ☐ Gauze Wrapped ☐ Torch Cut ☐ Drilled Holes ☐ Other (Specify)
☐ Louvered Shutter ☐ Key Punched ☐ Wire Wrapped ☐ Saw Cut ☐ None (Open Hole)

SCREEN-PERFORATED INTERVALS: From 24 ft. to 27 ft., From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 23.5 ft. to 27 ft., From ft. to ft., From ft. to ft.

9 GROUT MATERIAL: ☐ Neat cement ☒ Cement grout ☐ Bentonite ☐ Other
 Grout Intervals: From 0 ft. to 20.5 ft., From 20.5 ft. to 23.5 ft., From ft. to ft.

Nearest source of possible contamination:
☐ Septic Tank ☐ Lateral Lines ☐ Pit Privy ☐ Livestock Pens ☐ Insecticide Storage
☐ Sewer Lines ☐ Cess Pool ☐ Sewage Lagoon ☐ Fuel Storage ☐ Abandoned Water Well
☐ Watertight Sewer Lines ☐ Seepage Pit ☐ Feedyard ☐ Fertilizer Storage ☐ Oil Well/Gas Well
☒ Other (Specify) Former Chemical Commodities, Inc. Site
 Direction from well? SE Distance from well? ~305 ft.

10 FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	6	Hydrovac for Utility Clearance			
6	13.3	Silty Clay			
13.3	14	Weathered Rock, Sandy Clay			
14	16.5	Limestone			
16.5	18.5	Sandy Limestone			
18.5	21.25	Fine Sandstone			
21.25	22.5	Sandy Shale			
22.5	24.75	Shale			
24.75	27	Limestone			

Notes:

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo-day-yr) 12/11/2025... and this record is true to the best of my knowledge and belief.
 Kansas Water Well Contractor's License No. 1031... This Water Well Record was completed on (mo-day-yr) 12/19/2025 under the business name of Environmental Works, Inc. Signature Daniel Yoakum

	MONITORING WELL
	PIEZOMETER
	INJECTION WELL
	ABANDONED MONITORING WELL

 RESIDENCE

 Chemical Oxidation Trench Location

OFF-SITE CHEMICAL OXIDATION
DELIVERY SYSTEM LOCATION

 RAILROAD TRACKS

1. ALL LOCATIONS AND DIMENSIONS ARE APPROXIMATE.

2. * - UNABLE TO LOCATE WELL IN 2026

**HALEY
ALDRICH**

CHEMICAL COMMODITIES, INC.
OLATHE, KANSAS

WELL LOCATIONS

JANUARY 2026

FIGURE