

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

Application #28239

1. Location of well:		County Pottawatomie	Fraction 1/4 NW 1/4 SW 1/4	Section number 3	Township number T 10 S R 11 E	Range number 11
2. Distance and direction from nearest town or city: 1/4 Mile West & 1/2 Mile South of Belvue Street address of well location if in city:			3. Owner of well: Kansas Power & Light Co. R.R. or street: 818 Kansas Ave. City, state, zip code: Topeka, Kansas 66601			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: Jeffrey Energy Center Well No. 22		6. Bore hole dia. 54 in. Completion date 8/15/78 Well depth 76 ft.		
5. Type and color of material		From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
Sandy soil		0	2	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Fine sandy silt		2	15	9. Casing: Material Steel Height: Above XXXX Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 24 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 94.6 lbs./ft. Dia. 24 in. to 31 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 0.375 "		
Med. to coarse sand & gravel		15	35	10. Screen: Manufacturer's name Layne Type W.W. Dia. 36 " Slot/gauze 100 Length 40 Set between 31 ft. and 71 ft. Gravel pack? Yes Size range of material 1/8 x 3/8"		
Med. to coarse sand & gravel w/boulders		35	60	11. Static water level: 19 ft. below land surface Date 4/8/78		
Med. to coarse sand & gravel		60	76	12. Pumping level below land surfaces: 33 ft. after 8 hrs. pumping 3000 g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 4,200 g.p.m.		
Shale		76		13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>		
				14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade		
				15. Well grouted? Yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 20 ft.		
				16. Nearest source of possible contamination: ND* ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number 15 CHC HP 700 Volts 460 Length of drop pipe 70 ft. capacity 2900 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)						
18. Elevation: + - 959' Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley	19. Remarks: *Not Determined			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. <input type="checkbox"/> Address <input type="checkbox"/> Signed [Signature] Date 8-16-78 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5